

US ROCKIES REGION

Anadarko Daily Summary Report

Well: MEGAN H16-14

Project: COLORADO-WELD-NAD83-UTM13

Site: MEGAN H16-14

Rig name no.: BASIC 1549/1549

Event: ABANDONMENT

Start date: 4/16/2015

End date: 4/30/2015

Spud date: 8/4/1991

Active datum: RKB @4,846.99usft (above Mean Sea Level)

UWI: SE/SW/0/3/N/65/W/16/0/0/6/PRIME/S/660.00/W/0/1,920.00/0/0

Report no.	Report date	MD (usft)	24 hr summary
1	04/16/2015		MIRU Basic 1549. Kill well. ND well head. NU BOP. TOO. SI. SDFN.
2	04/20/2015		RU Warrior. Run gauge ring to 5220' & stopped. Pull gauge ring. Set CIBP @ 7070'. TIH to 7052'. RU Ridge Cementers. Set plug from 7052' to 6347' w/25 sks G cmt. LD tbg to 4411'. Set plug from 4411' to 3920' w/25 sks G cmt. LD tbg. Jet cut csg @ 1180'. SI.
3	04/21/2015		ND BOP. Unland csg. NU BOP. LD 37 jts of 3.5" csg. TIH w/40 jts tbg to 1288'. Hit bridge @ 315'. Had to circ tbg thru bridges to 1288'. RU Ridge Cementers. Spot plug from 1288' to 400' w/610 sks Type III cmt. Cementers had trouble pumping cmt.
4	04/22/2015		PU 3 jts tbg to tag cmt top @ 95'. LD tbg. ND BOP. RDMO Basic 1549.
5	04/30/2015		Dug up surface casing. Cut casing 6' below GL. Tagged @ 86'. Filled casing stub with 49 bags 5000# cement. Capped casing with a metal plate containing well info. Backfilled.
6	04/30/2015		TIME : 11:30, ROUTE : E12, WINS: H6408, PROJECT TYPE: P&A, PROD: CD, BATT#: 36159185, GATHERER: DCP, STATION: 212400, LINE : N/A, COMMENTS: P&A'd OFFLINE.