

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400824573

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER SIDETRACK

Refiling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☒

Date Received:

04/17/2015

Well Name: Long Well Number: 22-15-6NCH
Name of Operator: EDGE ENERGY LLC COGCC Operator Number: 10518
Address: 800 18TH STREET SUITE 300
City: DENVER State: CO Zip: 80202
Contact Name: Jeff Annable Phone: (303)928-7128 Fax: (303)218-5678
Email: regulatory@petro-fs.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20140065

WELL LOCATION INFORMATION

QtrQtr: NENW Sec: 22 Twp: 1N Rng: 65W Meridian: 6

Latitude: 40.043452

Longitude: -104.650917

Footage at Surface: 263 feet FNL/FSL FNL 2420 feet FEL/FWL FWL

Field Name: WATTENBERG Field Number: 90750

Ground Elevation: 5053 County: WELD

GPS Data:

Date of Measurement: 12/09/2014 PDOP Reading: 1.4 Instrument Operator's Name: Ben Hardenbergh

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 460 FSL 2639 FWL 460 FNL 2639 FWL
Sec: 15 Twp: 1N Rng: 65W Sec: 15 Twp: 1N Rng: 65W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.
(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 1 North, Range 65 West of the 6th PM
Section 15:All

Total Acres in Described Lease: 640 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 460 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 862 Feet
Building Unit: 862 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 253 Feet
Above Ground Utility: 289 Feet
Railroad: 4582 Feet
Property Line: 218 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone - as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 12/10/2014

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 377 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

Nearest wellbore permitted or completed in the same formation is the Long 22-15-2NBH.

Niobrara: Proposed Spacing Unit is described as the
Sec. 15: E2W2 & W2E2

OBJECTIVE FORMATIONS

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| NIOBRARA | NBRR | | 320 | GWA |

DRILLING PROGRAM

Proposed Total Measured Depth: 11849 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 377 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Land application

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Other

Other Disposal Description:

Drilling Fluids & Cuttings will be disposed of off-site at Land Application locations to be determined. A permitted location will be in place prior to use.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|
| SURF | 13+1/2 | 9+5/8 | 36 | 0 | 1200 | 660 | 1200 | 0 |
| 1ST | 8+3/4 | 7 | 26 | 0 | 7466 | 699 | 7466 | 3000 |
| 1ST LINER | 6+1/8 | 4+1/2 | 11.6 | 6704 | 11849 | | | |

☒ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

- ☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments Letter to the Director for COGCC Rule 318A.a. Exception Location Request, attached as Exception Loc Request.
COGCC Rule 318A.a. GWA Drilling Window waiver, attached as Exception Loc Waiver.
Letter to Director for COGCC Rule 318A.e. Proposed Spacing Unit, attached as Proposed Spacing Unit.
Nearest permitted or existing wellbore penetrating objective formation is Long 22-15-2NBH.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: 441625

Is this application being submitted with an Oil and Gas Location Assessment application? _____ No


I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jeff Annable

Title: Regulatory Technician Date: 4/17/2015 Email: regulatory@petro-fs.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 5/16/2015

Expiration Date: 05/15/2017

API NUMBER

05 123 41513 01

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

| | |
|--|---|
| | Operator shall comply with Buffer Zone Move-In, Rig-Up Notice Rule 305.h (effective 9/30/2014) |
| | 1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU. 2) Comply with Rule 317.j and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well. |

Best Management Practices

| No | <u>BMP/COA Type</u> | <u>Description</u> |
|----|--|--|
| 1 | Planning | <p>Rule 604.c(2)M. Fencing: A meeting with the surface owner will determine a fencing plan.</p> <p>Rule 804. Visual Impacts: All long term facility structures will be painted a color that enables the facilities to blend in with the natural background color of the landscape, as seen from a viewing distance and location typically used by the public. Maintain appearance with garbage clean-up; a trash bin will be located on site to accumulate waste by the personnel drilling the wells. Site will have unused equipment, trash and junk removed immediately.</p> |
| 2 | Traffic control | <p>604.c.(2)S. Access Roads: The access road will be constructed to accommodate local emergency vehicles. This road will be maintained for access at all times. Traffic will be routed to minimize local interruption. Dust control measures will also be utilized.</p> <p>604.c.(2)D: If required by the local government, a traffic plan shall be coordinated with the local jurisdiction prior to commencement of move in and rig up. Any subsequent modification to the traffic plan must be coordinated with the local jurisdiction.</p> |
| 3 | General Housekeeping | <p>Rule 604.c.(2)P. Trash Removal: All trash, debris and material not intrinsic to the operation of the oil and gas facility shall be removed and legally disposed of as applicable.</p> |
| 4 | Storm Water/Erosion Control | <p>Use water bars, and other measures to prevent erosion and non-source pollution. Implement and maintain BMPs to control stormwater runoff in a manner that minimizes erosion, transport of sediment offsite, and site degradation. Co-locate gas and water gathering lines whenever feasible, and mitigate any erosion problems that arise due to the construction of any pipeline(s).</p> |
| 5 | Material Handling and Spill Prevention | <p>Rule 604.c.(2)F. Leak Detention Plan: Pumper will visit the location daily and visually inspect all tanks and fittings for leaks. Additionally, monthly documented SPCCP inspections are conducted pursuant to 40 CFR 112.</p> <p>Rule 604.c.(2)R Tank Specifications: Tanks will be designed, constructed and maintained in accordance with NFPA Code 30. The tanks are visually inspected once a day for issues, and recorded inspections are conducted once a month.</p> |
| 6 | Construction | <p>Rule 604.c.(2).E. This will be a multi-well pad.</p> <p>Rule 604.c.(3)B. Berm Construction. Tank berms shall be constructed of steel rings with a synthetic or engineered liner and designed to contain 150% of the capacity of the largest tank. All berms will be visually checked periodically to ensure proper working condition. Secondary containment devices shall be sufficiently impervious to contain any spilled or released material. Tertiary containment, such as an earthen berm, will be installed around production facilities.</p> <p>Rule 803 Light sources during all phases of operations will be directed downwards and away from occupied structures where possible. Once the drilling and completion rigs leave the site, there will be no permanently installed lighting on site. Lighting shall be mounted at compressor stations on a pole or building and directed downward to illuminate key areas within the facility, while minimizing the amount of light projected outside the facility.</p> <p>Rule 604.c.(2).Q. All guy line anchors left buried for future use shall be identified by a marker of bright color not less than four (4) feet in height and not greater than one (1) foot east of the guy line anchor.</p> |
| 7 | Noise mitigation | <p>Rule 604.c.(2)A. Sound walls and/or hay bales will be used where necessary to surround the well site during drilling operations.</p> |

| | | |
|----|--------------------------------|---|
| 8 | Emissions mitigation | <p>Rule 604.c.(2)C.i. Green Completions - Emission Control System: Test separators and associated flow lines and sand traps shall be installed on-site to accommodate green completions techniques pursuant to COGCC Rules. In the anticipated absence of a viable gas sales line, the flowback gas shall be thermally oxidized in an emissions control device (ECD), which will be installed and kept in operable condition for least the first 90-days of production pursuant to CDPHE rules. This ECD shall have an adequate capacity for 1.5 times the largest flowback within a 10 mile radius, will be flanged to route gas to other or permanent oxidizing equipment and shall be provided with the equipment needed to maintain combustions where non-combustible gases are present.</p> |
| 9 | Odor mitigation | <p>Rule Rule 805: Oil & gas facilities and equipment shall be operated in such a manner that odors and dust do not constitute a nuisance or hazard to public welfare.</p> |
| 10 | Drilling/Completion Operations | <p>Rule 604.c.I: Upon initial rig-up and at least once every thirty (30) days during drilling operations thereafter, pressure testing of the casing string and each component of the blowout prevention equipment including flange connections shall be performed to seventy percent (70%) of working pressure or seventy percent (70%) of the internal yield of casing, whichever is less. Pressure testing shall be conducted and the documented results shall be retained by the operator for inspection by the Director for a period of one (1) year. Activation of the pipe rams for function testing shall be conducted on a daily basis when practicable.</p> <p>Rule 604.c.(2)L. Closed chamber drill stem tests shall be allowed. All other drill stem tests shall require approval by the Director. None planned for this well.</p> <p>Rule 604.c.(2).K. Drilling and Completion- Pit level Indicators shall be used on location. No pit is planned on this location.</p> <p>Rule 604.c.(2).O. Drilling and Completion-All loadlines shall be bullplugged or capped.</p> <p>Rule 317.p Logging Open hole resistivity log with gamma ray will be run on one of the first wells drilled on this pad to describe the stratigraphy of the vertical section of the wellbore and to adequately verify the setting depth of the surface casing and aquifer coverage. A CBL will be run on all production casing or, in the case of a production liner, the intermediate casing, when these casing strings are run. The Drilling Completion Report-Form 5 for every well on the pad shall identify which well was logged. Braden-head Monitoring: Operator acknowledges and will comply with COGCC Policyfor Braden-head Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.</p> <p>Anti-Collision: Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.</p> <p>Rule 604.c.(2)B.i Operator will be utilizing a closed loop system</p> <p>Blowout preventer equipment ("BOPE"). A double ram and annular preventer will be used during drilling. At least the drilling company shall have a valid well blowout prevention certifications.</p> <p>Rule 604.c.(2)J.ii Backup stabbing valves be required on well servicing operations during reverse circulation. Valves shall be pressure tested before each well servicingoperation using both low-pressure air and high-pressure fluid.</p> <p>BOPE for well servicing operations: Adequate BOP equipment shall be used. Stabbing valves shall be installed in the event of reverse circulation and shall be prior tested with low and high pressure fluid.</p> <p>event of reverse circulation and shall be prior tested with low and high pressure fluid.</p> |

| | | |
|----|-------------------|--|
| 11 | Final Reclamation | <p>Rule 604.c.(2)T. Within 90 days subsequent to the time of plugging and abandonment of the entire site, superfluous debris and equipment shall be removed from the site. Identification of plugged and abandoned wells will be identified pursuant to 319.a.(5)</p> <p>604.c.(2).U. Final Reclamation-The operator shall identify the location of the wellbore with a permanent monument as specified in Rule 319.a.(5). The operator shall also inscribe or imbed the well number and date of plugging upon the permanent monument.</p> |
|----|-------------------|--|

Total: 11 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

| <u>Att Doc Num</u> | <u>Name</u> |
|---------------------------|----------------------------|
| 400824573 | FORM 2 SUBMITTED |
| 400824615 | OffsetWellEvaluations Data |
| 400824629 | WELL LOCATION PLAT |
| 400826923 | DIRECTIONAL DATA |
| 400826924 | DEVIATED DRILLING PLAN |
| 400827034 | EXCEPTION LOC WAIVERS |
| 400827039 | PROPOSED SPACING UNIT |
| 400827831 | EXCEPTION LOC REQUEST |
| 400827832 | SURFACE AGRMT/SURETY |

Total Attach: 9 Files

General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|--------------------------|--|----------------------------|
| Permit | Final Review Completed. No LGD or public comment received. | 5/15/2015 3:54:13 PM |
| Permit | Added Location ID #441625 per operator. Permitting Review Complete. | 5/14/2015 10:35:52 AM |
| Permit | Open Hole Logging BMP submitted by operator. | 5/14/2015 10:35:51 AM |
| Engineer | Offset wells evaluated. | 5/13/2015 2:42:20 PM |
| Engineer | Changed sidetrack tab to yes (as written in other box) . | 5/13/2015 2:11:57 PM |
| Permit | Passed completeness. | 4/21/2015 7:45:06 AM |
| Permit | Proposed measured depth (MD) is rounded incorrectly - does not match imported data MD. Missing Surface Use Agreement (SUA). Exception location request does not meet COGCC requirements. Return to draft. | 4/20/2015 9:08:22 AM |

Total: 7 comment(s)