

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400841353

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322
2. Name of Operator: NOBLE ENERGY INC
3. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
4. Contact Name: Eileen Roberts
Phone: (303) 2284330
Fax: (303) 2284286
Email: eroberts@nobleenergyinc.com

5. API Number 05-123-39652-00
6. County: WELD
7. Well Name: Elway State
Well Number: LD01-75-1BHN
8. Location: QtrQtr: SWSE Section: 1 Township: 9N Range: 58W Meridian: 6
9. Field Name: WILDCAT Field Code: 99999

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 01/16/2015 End Date: 01/26/2015 Date of First Production this formation: 04/30/2015

Perforations Top: 6000 Bottom: 14517 No. Holes: 0 Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☒

Frac'd the Niobrara w/ 8195232 gals of Silverstim and Slick Water with 8411320#'s of Ottawa sand.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 195124 Max pressure during treatment (psi): 7186

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.74

Total acid used in treatment (bbl): 0 Number of staged intervals: 37

Recycled water used in treatment (bbl): 68785 Flowback volume recovered (bbl): 706

Fresh water used in treatment (bbl): 126338 Disposition method for flowback: RECYCLE

Total proppant used (lbs): 8411320 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 05/08/2015 Hours: 24 Bbl oil: 240 Mcf Gas: 16 Bbl H2O: 688

Calculated 24 hour rate: Bbl oil: 240 Mcf Gas: 16 Bbl H2O: 688 GOR: 66

Test Method: FLOWING Casing PSI: 438 Tubing PSI: 530 Choke Size: 24/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1268 API Gravity Oil: 38

Tubing Size: 2 + 3/8 Tubing Setting Depth: 5741 Tbg setting date: 04/28/2015 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Eileen Roberts _____

Title: Regulatory Analyst I _____

Date: _____

Email: eroberts@nobleenergyinc.com _____

:

Attachment Check List

Att Doc Num **Name**

--	--

Total Attach: 0 Files

General Comments

User Group **Comment**

Comment Date

--	--	--

Total: 0 comment(s)