

## US ROCKIES REGION

## Anadarko Daily Summary Report

Well: MAGNESS 34-26A

Project: COLORADO-WELD-NAD83-UTM13

Site: MAGNESS 34-26A

Rig name no.: ECWS 22/22

Event: WELL WORK EXPENSE

Start date: 4/29/2015

End date:

Spud date: 3/10/1994

Active datum: RKB @4,818.99usft (above Mean Sea Level)

UWI: 0/3/N/67/W/26/0/SESW/6/0/0/0/0/0/0

Report no.	Report date	MD (usft)	24 hr summary
1	04/29/2015		MIRU ECWS #22 TBG/CSG=200 BLEW DOWN TO WORK TANK CNTL W/ 15 BBLS DOWN TBG AND 30 BBLS DOWN CSG OF WATER W/ BIO NDWH NUBOP MIRU EMI TOO H W/ PROD TBG 230 JNTS 2.063 TBG. LD SN PU 3.5 RBP TIH SET @ 6905' ROLL HOLE TEST CSG TO 1000# GOOD TEST TOO H LD TBG
2	04/30/2015		SCP=0 WITH CLEAR FLUID NDBOP NDWH UNLAND CSG NU DUAL ENTRY EQUIP TIH W/ 90 JNTS 1/66" WORK STRING TO 2880' C&CH W/ TWO 2.5 GAL ALCOMER 74A SWEEPS SECURE WELL SDFN
3	05/04/2015		WELL DEAD CONTINUE TO TIH W/ 1/66" WORK STRING INTO OPEN HOLE DOWN TO 4880' C&CH W/ ALCOMER 74A SWEEPS SECURE WELL SDFN
4	05/05/2015		MIRU SANJEL PUMP 200 SKS "G" CEMENT AT 4848' TOO H W/ 115 JNTS EOT+1111' RU SANJEL PUMP 225 SKS TYPE III CEMENT ACROSS FH TOO H NDBOP ND DUAL ENTRY EQUIP RELAND 3.5" CSG NU NEW 5K WELL HEAD NUBOP LOAD WELL PREPARE FOR LOGGING SECURE WELL SDFN WOC
5	05/06/2015		MIRU WARRIOR E-LINE RUN CBL FROM 6531-SURFACE TOC=250' RD E-LINE TALLEY AND SINGLE IN W/ 2.063 TBG W/ RETRIEVING HEAD TAG SAND REVERSE CIRCULATE SAND OFF RBP LATCH ONTO RELEASE TOO H W/ RBP SECURE WELL SDFN
6	05/07/2015		WELL DEAD PU NC XN AND TIH W/ 2.063" TBG LAND PROD TBG W/ 226 JNTS @ 7369.30' BROACH TO XN NDBOP NUWH HYDROTEST TOP FLANGE CONNECTION TO 5000# GOOD TEST INSTALL PLUGS SWI RD MOVE RIG TO YARD