



02469479

05-007-07273
Loc # 313868Lease: Fort Morgan
Well #: 32API #: 0508707273
Location: Sec 25 Twn 3 N Rng 58W
County: Morgan
State: Colorado
Field: Fort Morgan
Operator: Colorado Interstate GasSpud Date: 07/27/1973
KB: 0
TD: 5558Plot Date: 07/29/2003
ELEV: 4347
PSTD: 5543

Description

9-5/8", 36#, K-55 Csg. 3 jts @ 78' GL

13-3/8", 48#, H-40 Csg. 7 jts Set @ 217' GL

Cmt. circ.

TD 17-1/2" Surface hole @ 225' GL

560-

1120-

1680-

2240-

2800-

3360-

3920-

4480-

5040-

Perf: 5496-5520' GL w/2 SPF (from perforators field ticket)

Perf: 5503' to 5527' GL w/2 SPF (from drilling report)

Cmt. circ.

5-1/2", 15.5#, K-55 Csg. Set @ 5553' GL

TD 7-7/8" hole @ 5558' GL