



05 007-07269
LOC # 313864

Lease: Fort Morgan
Well #: 28

Spud Date: 07/03/1973
KB: 0
TD: 5552

Plot Date: 02/05/1997
ELEV: 4344
PBTD: 5552

API #: 0508707269
Location: Sec 30 Twn 3 N Rng 57W
County: Morgan
State: Colorado
Field: Fort Morgan
Operator: Colorado Interstate Gas

	Description
0-	
5-75	
77-	9-5/8", 36#, K-55 Csg. 3 jts @ 80' GL
79-	Full Open Safety Valve @ 81' w/6 wraps hydraulic
81-	line counter clockwise @ surf.
85-215	
219-	Cmt. circ.
223-	13-3/8", 48#, H-40 Csg. 7jts Set @ 220' GL
227-	TD 17-1/2" Surface hole @ 227' GL
232-5483	
5493-	Perf: 5488' to 5496' GL w/2 SPF
5503-	
5513-	
5523-	Perf: 5499' to 5522' GL w/2 SPF
5533-	
5543-	5-1/2", 15.5#, K-55 Csg. 173 jts Set @ 5551' GL
	Cmt. circ.
	TD 7-7/8" hole @ 5552' GL