



02469381

LOC# 320703

Lease: Latigo  
Well #: 47

Spud Date: 08/14/1992  
KB: 0  
TD: 6869

Plat Date: 11/08/2005  
ELEV: 5460  
PBSD: 6838

API #: 05-005-06997-00  
Location: Sec 13 Twn 5S Rng 61W  
County: Arapahoe  
State: Colorado  
Field: Latigo Storage Field  
Operator: Colorado Interstate Gas Co.

## Description

Casing: 86.66' - 2 JTS- 9 5/8" -36#-K55-LTC-8RD CSG. SET AT 86' GL.  
Casing: 87.37' - 2 JTS- 5 1/2" -15.5# CSG. W/ BAKER SEAL ASSEMBLY. SET AT 86' GL.  
Casing: 121.74' - 3 JTS- 13 3/8" -54.5#-K55-STC-8RD CSG. SET AT 124' GL.  
TD 17-1/2" HOLE AT 145' GL

CEMENTED W/ 740 SKS STD CEMENT, CIRC.

Casing: 978.30' - 23 JTS- 8 5/8" -24#-K55-LTC-8RD CSG. SET AT 1102' GL.  
TD 12-1/4" HOLE AT 1111' GL.

Seating nipple @ 6704' GL.

214 jts, 6713.50', 2-3/8", 4.7#, J55, 8R, EUE tbg

Baker LOK-SET packer @ 6708' GL w/4,000# comp.

PERF: 6734' - 6758'; 6738' - 6746'; 6748' - 6758' GL W/ 4 SPF.  
FORMATION: "J2" SAND

Casing: 6778.93' - 5 1/2" -15.5#-K55-LTC-8RD CSG. SET AT 6863' GL.  
CEMENTED W/ 1150 SKS HLC + 225 SKS 50-50 POZ, CIRC.

TD 7-7/8" HOLE AT 6869' GL.

PBSD AT 6838' GL

Rec: 11-11-05