



02469378

05-005-00100
Loc# 320771Lease: LATIGO
Well #: 44Spud Date: 05/25/1990
KB: 0
TD: 6790Plot Date: 06/12/1990
ELEV: 5412
PBD: 6761API #: 05-005-06968-00
Location: Sec 24 Twn 5S Rng 61W
County: ARAPAHOE
State: COLORADO
Field: LATIGO
Operator: COLORADO INTERSTATE GAS CO.

Description

Casing: 1019.57' - 24 JTS - 8 5/8" - 24# - K55 - 8RD CSG. SET AT 1021' GL.

Cement: 600 SX. HALL. STANDARD CEMENT. CIRC.

Hole: TD 12 1/4" HOLE AT 1023' GL.

Perf: 6666' - 6688'; 6690' - 6696' GL. W/ 4 SPF.

Formation: 'J2' SAND

Casing: 6783.86' - 160 JTS. - 5 1/2" - 15.5# - K55 CSG. SET AT 6780' GL.

Cement: 1100 SKS. HLC + 225 SKS. 50/50 POZMIX. CIRC.

Hole: TD 7 7/8" HOLE AT 6790' GL.