



02469375

Loc # 302656

Lease: Latigo  
Well #: 41

Spud Date: 04/19/1979  
KB: 0  
TD: 6842

Plot Date: 08/31/2006  
ELEV: 5462  
PBD: 6810

API #: 05-005-06373-00  
Location: Sec 24 Twn 5S Rng 61W  
County: Arapahoe  
State: Colorado  
Field: Latigo Storage Field  
Operator: Colorado Interstate Gas Co.

## Description

67.03' - 2 JTS. - 9 5/8" - 36# - K55 - LTC CSG. SET AT 68' GL.

68.96' - 2 JTS. - 5 1/2" - 15.5# - K55 CSG W/ BAKER SEAL  
ASSEMBLY SET AT 68' GL.

134.87' - 3 JTS. - 13 3/8" - 54.5# - K55 CSG. SET AT 135' GL.

17 1/2" REAMED HOLE TO 165' GL

CEMENTED W/ 625 SKS IDEAL TYPE II CEMENT. CIRC.

366.69' - 21 JTS. - 8 5/8" 24# K55 CSG. SET AT 1002' GL.

TD 12 1/4" HOLE AT 1012' GL

## Reservoir Services

SEP 06 2006

\_\_\_ LDK

\_\_\_ JGZ

\_\_\_ APT

\_\_\_ CRD

COPY  
FILE  
SCAN

6699.33' - 226 JTS - 2 3/8" - 4.7# - J55 - 8RD - EUE.

Seating Nipple at 6687' GL

Baker Model R-3 Double Grip Casing Packer set @ 6694' GL  
w/20,000# compression

PERF: 6738' - 6754'; 6756' - 6760'; 6762' - 6766' GL W/ 2 SPF

Formation: 'J2' SAND

CEMENTED W/ 1168 SKS HLC + 225 SKS 50-50 POZ. CIRC.

6760.40' - 163 JTS. - 5 1/2" - 15.5# - K55 - LTC CSG. SET AT  
6829' GL.

TD 7 7/8" HOLE AT 6842' GL