



05-005-70001
Loc # 320827

Lease: LATIGO
Well #: 35

Spud Date: 05/30/1978
KB: 0
TD: 6840

Plot Date: 08/31/2006
ELEV: 5488
PBD: 6818

API #: 05-005-40001-00
Location: Sec 25 Twn 5S Rng 61W
County: ARAPAHOE
State: COLORADO
Field: LATIGO
Operator: COLORADO INTERSTATE GAS CO.

Description

Casing: 997.66' - 24 JTS - 8 5/8" - 24# - K55 - BRD CSG. SET AT 998' GL.
Cement: 600 SX. IDEAL TYPE II CEMENT. CIRC.
Hole: TD 12 1/4" HOLE AT 1005' GL.

Reservoir Services

SEP 06 2006

___ LDK ___ JCS CUP:
___ APT ___ CRD FILE
SCA

Removed tubing

Perf: 6732' - 6735'; 6742' - 6749' GL. W/ 2 SPF.
Formation: 'J2' SAND

Casing: 6832.00' - 166 JTS. - 5 1/2" - 15.5# - K55 CSG. SET AT 6832' GL.
Cement: 1215 SKS. HLC + 225 SKS. 50/50 POZMIX. CIRC.
Hole: TD 7 7/8" HOLE AT 6840' GL.