



**Description**

88.60' - 3 JTS. - 9 5/8" - 36# - K55 - LTC CSG. SET AT 90' GL.  
 90.75' - 3 jts. - 5 1/2" - 15.5# - K55 CSG W/ BAKER SEAL ASSEMBLY SET AT 90' GL.  
 132.82' - 4 JTS. - 13 3/8" - 54.5# - K55 CSG. SET AT 135' GL.  
 17 1/2" REAMED HOLE TO 150' GL

CEMENTED W/ 625 SKS "G" CEMENT. CIRC.

865.12' - 22 JTS. - 8 5/8" 24# K55 CSG. SET AT 1000' GL.  
 TD 12 1/4" HOLE AT 1007' GL

**Reservoir Services**

OCT 16 2006

\_\_\_ LDK      \_\_\_ J24      GL  
 \_\_\_ APT      \_\_\_ CRD      FIL  
    SC

6565.70' - 210 jts - 2-3/8" - 4.7# - J55-8R-EUE tbg w/SN & collar on btm. Set @ 6562' GL  
 PERF: 6716' - 6738' GL W/ 4 SPF

Re-perforated 6716' - 6736' GL w/4 SPF on 9/07/06

Formation: "J2" SAND

Tagged frac sand @ 6615' GL on 10/05/06

6723.45' - 172 JTS. - 5 1/2" - 15.5# - K55 - LTC CSG. SET AT 6814' GL.  
 CEMENTED W/ 1164 SKS HLC + 225 SKS 50-50 POZ. CIRC.  
 TD 7 7/8" HOLE AT 6820' GL