



02469357

05-005-06745  
Loc # 320725Lease: Latigo  
Well #: 23Spud Date: 02/26/1977  
KB: 0  
TD: 6933Plot Date: 08/10/2004  
ELEV: 5463  
PBD: 6914API #: 05-005-06745-00  
Location: Sec 13 Twn 5S Rng 61W  
County: Arapahoe  
State: Colorado  
Field: Latigo Storage Field  
Operator: Colorado Interstate Gas Co.

## Description

72.96' - 2 JTS. - 9 5/8" - 36# CSG. SET AT 74' GL.

74.88' - 5 1/2" - 15.5# CSG W/ BAKER SEAL ASSEMBLY SET AT 74' GL.

17 1/4" REAMED HOLE TO 132' GL

130.04' - 3 JTS. - 13 3/8" - 54.5# CSG. SET AT 132' GL.

CEMENTED W/ 700 SKS. "G" CEMENT. CIRC.

866.58' - 21 JTS. - 8 5/8" - 24# CSG. SET AT 999' GL.

TD 12 1/4" HOLE AT 1010' GL

Baker Lok-Set packer @ 6706' GL w/8,000# compression.

Seating Nipple @ 6701' GL

Tubing: 6711.52' - 215 JTS. - 2 3/8" - 4.7# - J55 - 8RD EUE TBG.

PERF: 6744' - 6764' GL W/ 3 SPF

Formation: "J2" SAND

PBD @ 6914' GL

6853.88' - 211 JTS. - 5 1/2" - 15.5# - K55 CSG. SET AT 6928' GL.

CEMENTED W/ 1315 SKS HLC + 250 SKS 50-50 POZ. CIRC.

TD 7 7/8" HOLE AT 6933' GL