



02469354

05-005-06 #16  
LOC # 320714Lease: Latigo  
Well #: 20Spud Date: 03/19/1976  
KB: 0  
TD: 6825Plot Date: 08/10/2004  
ELEV: 5422  
PBD: 6808API #: 05-005-06716-00  
Location: Sec 13 Twn 5S Rng 61W  
County: Arapahoe  
State: Colorado  
Field: Latigo Storage Field  
Operator: Colorado Interstate Gas Co.

## Description

89' - 9 5/8" - 32# CSG. SET AT 85' GL.  
 90' - 5 1/2" - 15.5# CSG W/ BAKER SEAL ASSEMBLY SET AT 85' GL.  
 92' - 13 3/8" - 48# CSG. SET AT 92' GL.  
 17 1/4" REAMED HOLE TO 100' GL

TD 12 1/4" HOLE AT 889' GL  
 CEMENTED W/ 700 SKS CEMENT.  
 793' - 8 5/8" 24# CSG. SET AT 889' GL.

Tubing: 6651.58' - 216 jts - 2 3/8" - 4.7# - J55 - 8RD EUE TBG.  
 Baker Lok-Set packer @ 6647' GL w/11,000# compression.  
 Seating Nipple @ 6642'

PERF: 6683' - 6690' & 6694' - 6704' GL W/ 2 SPF  
 Formation: 'J2' SAND

PBD @ 6808' GL  
 TD 7 7/8" HOLE AT 6825' GL  
 6740' - 5 1/2" - 15.5# CSG. SET AT 6825' GL.  
 CEMENTED W/ 1600 SKS HLC + 275 SKS 50-50 POZ. CIRC.