



02469353

05-005 06715
Loc # 320713Lease: Latigo
Well #: 19Spud Date: 03/11/1976
KB: 0
TD: 6865Plot Date: 08/10/2004
ELEV: 5443
PBD: 6839API #: 05-005-06715-00
Location: Sec 13 Twn 5S Rng 61W
County: Arapahoe
State: Colorado
Field: Latigo Storage Field
Operator: Colorado Interstate Gas Co.

Description

90' - 9 5/8" - 32# CSG. SET AT 90' GL.

92.47' - 5 1/2" - 15.5# CSG W/ BAKER SEAL ASSEMBLY SET AT 90' GL.

123' - 13 3/8" - 48# CSG. SET AT 123' GL.

17 1/4" REAMED HOLE TO 150' GL

CEMENTED W/ 700 SKS CEMENT. CIRC.

8 5/8" 24# CSG. SET AT 874' GL.

TO 12 1/4" HOLE AT 886' GL

Baker Lok-Set packer @ 6702' GL w/10,000# compression.

Seating Nipple @ 6697'

Tubing: 6707.64' - 213 jts - 2 3/8" - 4.7# - J55 - 8RD EUE TBG.

PERF: 6726' - 6754' GL W/ 4 SPF on 7/13/04

Formation: J2 SAND

TO 7 7/8" HOLE AT 6865' GL

PBD AT 6839' GL

CEMENTED W/ 1200 SKS HLC + 225 SKS 50-50 POZ, CIRC.

6717' - 5 1/2" - 15.5# CSG. SET AT 6865' GL.