



05-005-00004  
Loc# 320710

Lease: LATIGO  
Well #: 18

Spud Date: 04/20/1978  
KB: 0  
TD: 6721

Plot Date: 08/31/2006  
ELEV: 5384  
PBD: 6704

API #: 05-005-06689-00  
Location: Sec 18 Twn 5S Rng 60W  
County: ARAPAHOE  
State: COLORADO  
Field: LATIGO  
Operator: COLORADO INTERSTATE GAS CO.

Description

Casing: 8 5/8" - 24# CSG. SET AT 843' GL.

Cement: 700 SX. CIRC.

Hole: TD 12 1/4" HOLE AT 854' GL.

Reservoir Services

SEP 06 2006

\_\_\_ LDK    \_\_\_ JDS    COPY  
\_\_\_ APT    \_\_\_ CRD    FILE  
                             SCAN

6640.01' - 213 JTS & 2 subs - 2 3/8" - 4.7# - J55 - 8R - EUE.  
Subs below 1st jt.  
Seating Nipple @ 6635' GL

Baker Model A-3 Lok-Set packer @ 6638' GL w/12,000#  
compression

Perf: 6663' - 6666' & 6670' - 6676' GL. W/ 2 SPF.

Formation: "J2" SAND

PBD @ 6704' GL

Hole: TD 7 7/8" HOLE AT 6821' GL.

Cement: 1275 SKS. HLC + 225 SKS. 50/50 POZMIX. CIRC.

Casing: 6721.08' - 169 JTS. - 5 1/2" - 15.5# - K55 CSG. SET AT  
6721' GL.