



02469351

US-000-06551

LOC # 320647

Lease: LATIGO
Well #: 15Spud Date: 06/08/1972
KB: 0
TD: 6811Plot Date: 07/16/2003
ELEV: 5443
PBD: 6771API #: 05-205-06331-20
Location: Sec 19 Twn 5S Rng 60W
County: ARAPAHOE
State: COLORADO
Field: LATIGO
Operator: COLORADO INTERSTATE GAS CO.

Description

Hole: TD 12 1/4" HOLE AT 203' GL.

Casing: 6 JTS. - 8 5/8" - 24# CSG. SET AT 203' GL.

Cement: 200 SX REG. W/ 2% CACL & 1/4# FLOCELE/SX.

Cement: STAGE TWO: 200 SX. 50/50 POZMIX.

DV Tool @ 931'

APPROX. TOP OF CEMENT @ 5720' GL. (CALCULATED)

Baker Lok-Set packer @ 6638' GL in neutral. SN @ 6634' GL

213 JTS & 2 subs - 6639.63' - 2 3/8" - 4.7# - J55-8R-EUE TBG. Subs below 1st jt.

Perf: 6681' - 6685'; 6689' - 6693'; & 6699' - 6703' GL W/ 2 SPF.

PBD @ 6771'

Hole: TD 7 7/8" HOLE AT 6811' GL.

Casing: 220 JTS. - 4 1/2" - 10.5# & 11.6# CSG. SET AT 6811' GL.

Cement: STAGE ONE - 200 SX. 50-50 POZ.