



US-005-06214
LOC # 320631

Lease: LATIGO
Well #: 08

Spud Date: 03/13/1971
KB: 0
TD: 6834

Plot Date: 07/16/2003
ELEV: 5445
PBTD: 6793

API #: 05-005-06214-00
Location: Sec 24 Twn 5S Rng 61W
County: ARAPAHOE
State: COLORADO
Field: LATIGO
Operator: COLORADO INTERSTATE GAS CO.

Description

Casing: 1005.63' - 32 JTS. - 8 5/8" - 24# - K55 - CSG. SET AT 995' GL.
Cement: 300 SKS. 50-50 POZ MIX FOLLOWED BY 200 SKS. G CEMENT. CIRC.
Hole: TD 12 1/4" HOLE AT 998' GL.

APPROX. TOP OF CEMENT @ 5600' GL. (CALCULATED)

Baker Lok-Set packer @ 6713' GL w/12,000# compression. SN @ 6708' GL
218 JTS & 3 subs - 6714.67' - 2 3/8" - 4.7# - J55-8R-EUE TBG. Subs below 1st jt.
Perf: 6730' - 6736' W/ 2 SPF.

Perf: 6749' - 6751' GL W/ 2 SPF.

PBTD @ 6793'

Hole: TD 7 7/8" HOLE AT 6834' GL.

Casing: 6857.36' - 209 JTS. - 5 1/2" - 14# & 15.5# - CSG. SET AT 6834' GL.
Cement: 175 SX. 50-50 POZ W/ 4% GEL, .75% CTR-2, & 10% FALT.