



LOC # 320638

Lease: LATIGO
Well #: 07

Spud Date: 08/20/1971
KB: 0
TD: 6843

Plot Date: 07/16/2003
ELEV: 5463
PBD: 6785

API #: 05-005-06264-00
Location: Sec 24 Twn 5S Rng 61W
County: ARAPAHOE
State: COLORADO
Field: LATIGO
Operator: COLORADO INTERSTATE GAS CO.

Description

Hole: TD 12 1/4" HOLE AT 190' GL.

Casing: 8 5/8" - 24# - K55 - CSG. SET AT 190' GL.

Cement: 200 SKS. W/ 3% CCL. CIRC.

Obstruction 6500'

APPROX. TOP OF CEMENT @ 5780' GL. (CALCULATED)

Baker Lok-Set packer @ 6716' GL w/10,000# compression. SN @ 6711' GL

216 JTS & 2subs - 6718.41' - 2 3/8" - 4.7# - J55 - 8R - EVE TBG. Subs below 1st stand.

Perf: 6744' - 6775' GL W/ 2 SPF.

Perf: 6775' - 6779' W/ 3 SPF.

Perf: 6777' - 6780' W/ 4 SPF.

PBD @ 6785'

Casing: 5 1/2" - 14# & 15.5# - CSG. SET AT 6832' GL.

Cement: 150 SX. 50-50 POZ W/ 3% CCL.

Hole: TD 7 7/8" HOLE AT 6843' GL.