



02469348

05-005-06105  
Loc # 320626Lease: LATIGO  
Well #: 11Spud Date: 05/11/1978  
KB: 0  
TD: 6821Plot Date: 07/01/1978  
ELEV: 5393  
PBTD: 6799API #: 05-005-06103-00  
Location: Sec 14 Twn 5S Rng 61W  
County: ARAPAHOE  
State: COLORADO  
Field: LATIGO  
Operator: COLORADO INTERSTATE GAS CO.

## Description

Hole: TD 12 1/4' HOLE AT 123' GL.

Cement: 120 SKS. CIRC.

Casing: 119' - 8 5/8" - 24# CSG. SET AT 123' GL.

Perf: 6719' - 6735' &amp; 6738' - 6745' GL. W/ 2 SPF.

Formation: 'J2' SAND

Casing: 6819' - 172 JTS. - 5 1/2" - 15.5# - K55 CSG. SET AT  
6819' GL.

Cement: 1375 SX. HLC &amp; 225 SKS. 50-50 POZ. CIRC.

Hole: TD 7 7/8' HOLE AT 6821' GL.