



05-005-06210  
LOC # 320630

Lease: LATIGO  
Well #: 09

Spud Date: 02/28/1971  
KB: 0  
TD: 6897

Plot Date: 07/29/2003  
ELEV: 5503  
PBTD: 6849

API #: 05-005-06210-00  
Location: Sec 23 Twn 5S Rng 61W  
County: ARAPAHOE  
State: COLORADO  
Field: LATIGO  
Operator: COLORADO INTERSTATE GAS CO.

Description

Hole: TD 12 1/4" HOLE AT 160' GL.

Casing: 158.50' - 8 5/8" CSG. SET AT 160' GL.

Cement: 150 SKS. CEMENT

Cement: STAGE TWO: 200 SX. 50/50 POZMIX W/ 2% GEL.

DV Tool @ 1009'

APPROX. TOP OF CEMENT @ 5810' GL. (CALCULATED)

Seating Nipple @ 6759'

Baker LokSet Pkr in 10,000# Comp @ 6763'

6762.57', 222 Jts, 2-3/8", 4.7#, J-55, 8R EUE Tbg @ 6763'

Perf: 6801-6807 GL. W/ 2 SPF.

Perf: 6807' - 6812' GL W/ 4 SPF.

Perf: 6811' - 6814' GL W/ 4 SPF.

Perf: 6813' - 6815' GL W/ 4 SPF.

PBTD @ 6849'

Casing: 6876.23' - 211 JTS. - 5 1/2" - 15.5# & 14# - K55- STC  
CSG. SET AT 6880' GL.

Cement: STAGE ONE - 150 SX. 50-50 POZ W/ 3% CCL.

Hole: TD 7 7/8" HOLE AT 6897' GL.