

RECEIVED
JUL 27 1982

File

CRD1-1561

File in duplicate for Parented and Federal Lands
File in triplicate for State lands.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT-" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input checked="" type="checkbox"/> Water Injector		5. LEASE DESIGNATION & SERIAL NO. FEE	
2. NAME OF OPERATOR CHEVRON U.S.A. Inc.,		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
3. ADDRESS OF OPERATOR 695 Chevron Road, Rangely, CO., 81648		7. UNIT AGREEMENT NAME Rangely Weber Sand Unit	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 1350' FNL & 1271' FEL of Sec. 33 At proposed prod. zone as above		8. FARM OR LEASE NAME FEE	
14. PERMIT NO.		9. WELL NO. 94X	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) KB - 5296		10. FIELD AND POOL, OR WILDCAT Rangely	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 33 T2N, R102W, 6th P.M.	
		12. COUNTY Rio Blanco	13. STATE Colorado

16. Check Appropriate Box To Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) C/O, Liner, Perf, B/D Frac & SIE X	
(Other)		(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

18. Date of work 11-16-81 to 1-29-82 * Must be accompanied by a cement verification report.

- MIR. NU BOP's. POOH w/short & long string. C/O to 6420' (PBD).
- Ran 5" liner. Top of liner at 5497', bottom of liner at 6419'. Cemented w/70 sxs Mod. S S cement and 100 sxs Class "G" cement. Clean out to 6420'.
- Perforated w/3 SPF at 6332, 6290-88, 6278-76, 6267, 6255, 6245, 6197, 6189, 6157, 6152-50-, 6132, 6127, 6123, 6056-54, 6046-44, 6010, 6002, 5994-92, 5945, 5930, 5916, 5896-94, 5757-55, 5676-74, 5648, 5642, 5636'. B/D using source water, 15% HCL and RCN balls.
- Fraced well using 10,600 gals. YF4PSD and 2,400 lbs. 20/40 sand.
- RIH w/injection string, landed at 6375.18'. Packers at 5446, 5740, 5836, 5976, 6034, 6095, 6228'. R/D and placed well on injection.

DVR
FJ
MHM
JAN
JJD
RLS
CGM

19. I hereby certify that the foregoing is true and correct

SIGNED Roy Chambers, Jr. TITLE Unit Supt. DATE 7-21-82

(This space for Federal or State office use)

APPROVED BY D.T. Rogers TITLE DIRECTOR O & G Cons. Comm. DATE AUG 9 1982

CONDITIONS OF APPROVAL, IF ANY: