

Remittance Address:

Select Well Service

PO Box 203997

Dallas, TX 75320-3997

Phone 303.651.0801 Fax 303.651.6219



Date	Invoice #	Page
08/29/13	SI591104	1

Pro Forma Invoice

Bill To:		Ship To:	
NOBLE ENERGY, INC 804 GRAND AVE. PLATTEVILLE, CO 80651		NOBLE ENERGY, INC 804 GRAND AVE. PLATTEVILLE, CO 80651	
PO No.	Terms	Due Date	Ordered By
		09/28/13	CHUCK EMERS
Net 30 Days			
		Main Code	Sub Code
			AFE #
		End Date of Work 08/23/13	
		Lease Name FEDERAL PERRY 2-44 08-30	

8/15/13 TICKET NO. 775

CREW TRIED TO MOVE RIG- NO LUCK; 8 HOURS STAND

BY TIME.

8/16/13 TICKET NO. 776

CREW TRAVEL TO LOCATION; IT WAS STILL TOO WET TO
GET THE RIG ON BLM LOCATION; SO CREW TRAVEL TO

YARD; 8 HRS STAND BY.

8/17/13 TICKET NO. 777

CREW TRAVEL TO LOCATION; MOVED RIG & EQUIPMENT
IN IT WAS DRY ENOUGH; RIG HOOK UP PUMP & TANK;

TALLY FIRST ROW OF TUBING & COLLARS; PICK UP

4 DRILL COLLARS & BIT; DIDNT TAG; WENT TO RELEASE

THE BRAKES ON THE RIG; NO LUCK; TRY TO FIX IT

OURSELVES; HAD TO CALL THE MECHANIC TO FIX IT.

8/18/13 TICKET NO. 778

CREW TRAVEL TO LOCATION; STAND DRILL COLLARS IN

THE DERRICK; TAKE BOP OFF WELL; TAKE WELLHEAD OFF;

PUT NEW ONE ON; PUT BOP BACK ON; RUN THE COLLARS

BACK IN & PICK UP 2 JOINTS OF TUBING; CLOSE PIPE

RAMS TEST SURFACE TO 200PSI; IT HELD; DRILL OUT

TOP PLUG & WAS GETTING CEMENT & METAL; GOT DOWN

TO ALMOST 100'; ROLL THE HOLE; PULL TUBING; CLOSE

WELL IN; CREW TRAVEL TO YARD.

8/19/13 TICKET NO. 779

CREW TRAVEL TO LOCATION; RUN TUBING OUT OF THE

DERRICK; TAGGED SOMETHING HARD; WASHED IT BY

IT GOT TO NEXT CEMENT PLUG; DRILLED IT OUT; GOT

Remittance Address:

Select Well Service

PO Box 203997

Dallas, TX 75320-3997

Phone 303.651.0801 Fax 303.651.6219



Date	Invoice #	Page
08/29/13	SI591104	2

Pro Forma Invoice

Bill To:		NOBLE ENERGY, INC		804 GRAND AVE.		PLATTEVILLE, CO 80651	
Ship To:		NOBLE ENERGY, INC		804 GRAND AVE.		PLATTEVILLE, CO 80651	
PO No.	Terms	Due Date	Ordered By	Attention	Main Code	Sub Code	AFE #
	Net 30 Days	09/28/13	CHUCK EMERS				AFE
Lease Name FEDERAL PERRY 2-4-44 08-30							
End Date of Work 08/23/13							

TO 3130; ROLL THE HOLE; PULL TUBING; CLOSE WELL IN; CREW TRAVEL TO YARD.

8/20/13 TICKET NO. 780

CREW TRAVEL TO LOCATION; RUN IN THE HOLE WITH TUBING & WASHED DOWN TO 6133; ROLLED THE HOLE BOTTOMS UP TWICE; PULL TUBING; LAYED DOWN THE DRILL COLLARS; HUT THE WELL IN; CREW TRAVEL TO YARD.

8/21/13 TICKET NO. 781

CREW TRAVEL TO LOCATION; CHECK PRESSURE WAS NONE; RUN TUBING IN TO 562 & IT STACKED OUT; TRIED DRILLING ON IT WITH NOTCHED COLLAR- NO LUCK; SO PULL TUBING BACK OUT; PUT ONE DRILL COLLAR ON & BIT; WENT BACK IN & REAMED THE HOLE; PULLED BACK OUT & TRIED TO GET IN; GOT IN & DOWN TO 6133; ROLLED THE HOLE WHILE WE HAD A SAFETY MEETING; HOOKED UP CEMENTERS; PUMPED PLUG; PULLED 20 STANDS; WAITED 1 HR & 20 MIN; IT ACTED LIKE NO PLUG WAS THERE; PULLED 20 AGAIN; WAIT 25 MIN; THEN PULLED PIPE OUT OF THE HOLE; WET STRING ALL THE WAY OUT; HAD 19 JOINTS OF TUBING FULL OF CEMENT; WAS UNABLE TO GET THE CEMENT OUT OF THE TUBING SO PUT THEM OFF TO THE SIDE; CLEANED UP TOOLS & CLOSED THE WELL IN FOR THE NIGHT; CREW TRAVEL TO THE YARD.

WORKOVER RIG (4 MAN CREW)
CREW TRAVEL
BASE BEAM RENTAL
BLOWOUT PREVENTOR

13.5	Hour	280.00	3,780.00
2	Day	200.00	400.00
1	Day	50.00	50.00
1	Day	300.00	300.00

Remittance Address:

Select Well Service

PO Box 203997
Dallas, TX 75320-3997
Phone 303.651.0801 Fax 303.651.6219



Pro Forma Invoice		
Date	Invoice #	Page
08/29/13	SI591104	3

Bill To:		Ship To:	
NOBLE ENERGY, INC 804 GRAND AVE. PLATTEVILLE, CO 80651		NOBLE ENERGY, INC 804 GRAND AVE. PLATTEVILLE, CO 80651	
PO No.	Terms	Due Date	Ordered By
			Attention
			Main Code
			Sub Code
			A/E #
Lease Name		End Date of Work	
FEDERAL PERRY 2-4-44 28-30		08/23/13	

Description	Qty	UOM	Unit Price	Total Price
-------------	-----	-----	------------	-------------

WASHINGTON HEAD	1	Day	175.00	175.00
2.5 POWER SWIVEL	1	Day	650.00	650.00
PUMP & TANK	1	Day	550.00	550.00
PIPE DOPE	1	Each	36.00	36.00
TUBING WIPER RUBBERS	1	Each	44.00	44.00

8/22/13 TICKET NO. 782				
CREW TRAVEL TO LOCATION; RUN IN THE HOLE & TAG				
BOTTOM PLUG; IT WAS THERE SO LAY DOWN TO THE				
NEXT PLUG WITH 97 JOINTS IN THE HOLE 3033' PUMP				
IT; PULL TUBING; WAIT 3 HRS; RUN IN THE HOLE & TAG				
IT; IT WAS THERE SO LAY DOWN TO 1320'; PUMP 700				
SACKS; LOST CIRCULATION; SO PULL TUBING; CLEAN UP				
ALL TOOLS; CLOSE WELL IN FOR THE NIGHT; CREW				
TRAVEL TO YARD.				
WORKOVER RIG (4 MAN CREW)	11	Hour	280.00	3,080.00
CREW TRAVEL	2	Day	200.00	400.00
BASE BEAM RENTAL	1	Day	50.00	50.00
BLOWOUT PREVENTOR	1	Day	300.00	300.00
WASHINGTON HEAD	1	Day	175.00	175.00
PUMP & TANK	1	Day	550.00	550.00
PIPE DOPE	1	Each	36.00	36.00
8/23/13 TICKET NO. 783				
CREW TRAVEL TO LOCATION; RUN IN THE HOLE & TAGGED				
WITH 12 JOINTS; 375'; RIG UP BACKER & PUMP; DOUBLE				
THE CAPACITY OF CEMENT; GOT CEMENT TO SURFACE;				
LAY DOWN TUBING; STRIP BOP OFF WELL; TAKE IT APART				
& GET ALL THE CEMENT OUT OF BOP; RACK IT ON BEAM;				
RIG DOWN; PARK RIG OFF OF BLM GROUND; HELP				
WELDER CAP WELL; WHILE THE CREW RACKED THE PUMP				