

**FORM
INSP**Rev
05/11**State of Colorado
Oil and Gas Conservation Commission**1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

DE	ET	OE	ES
----	----	----	----

Inspection Date:

05/24/2015

Document Number:

675101442

Overall Inspection:

SATISFACTORY**FIELD INSPECTION FORM**

Location Identifier	Facility ID	Loc ID	Inspector Name:	On-Site Inspection	2A Doc Num:
	437501	434288	GRANAHAH, KYLE	<input type="checkbox"/>	

Operator Information:OGCC Operator Number: 96850Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLCAddress: 1001 17TH STREET - SUITE #1200City: DENVER State: CO Zip: 80202

- ☐ THIS IS A FOLLOW UP INSPECTION
- ☐ FOLLOW UP INSPECTION REQUIRED
- ☒ NO FOLLOW UP INSPECTION REQUIRED
- ☐ INSPECTOR REQUESTS FORM 42 WHEN CORRECTIVE ACTIONS ARE COMPLETED

Contact Information:

Contact Name	Phone	Email	Comment
, WPX		COGCCInspectionReports@wpxenergy.com	All inspections

Compliance Summary:QtrQtr: LOT14 Sec: 29 Twp: 2S Range: 98W

Insp. Date	Doc Num	Insp. Type	Insp Status	Satisfactory /Action Required	PA P/F/I	Pas/Fail (P/F)	Violation (Y/N)
12/16/2014	675100793	DG	PR	ACTION REQUIRED			No

Inspector Comment:On location to witness perfs reshot between 13393' & 13535' to frac formation.**Related Facilities:**

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
434301	WELL	PR	02/09/2015	LO	103-11993	FEDERAL RG 421-32-298	PR
434302	WELL	PR	03/23/2015	LO	103-11994	FEDERAL RG 24-29-298	PR
437501	WELL	PR	02/09/2015		103-12120	FEDERAL RG 713-29-298	WO

Equipment:**Location Inventory**

Special Purpose Pits: _____	Drilling Pits: _____	Wells: <u>6</u>	Production Pits: _____
Condensate Tanks: _____	Water Tanks: <u>3</u>	Separators: <u>6</u>	Electric Motors: _____
Gas or Diesel Mortors: _____	Cavity Pumps: _____	LACT Unit: _____	Pump Jacks: _____
Electric Generators: _____	Gas Pipeline: <u>1</u>	Oil Pipeline: _____	Water Pipeline: _____
Gas Compressors: _____	VOC Combustor: _____	Oil Tanks: <u>5</u>	Dehydrator Units: _____
Multi-Well Pits: _____	Pigging Station: _____	Flare: _____	Fuel Tanks: _____

Location

Emergency Contact Number (S/A/V): _____

Corrective Date: _____

Comment: _____

Inspector Name: GRANAHAN, KYLE

Corrective Action:

Spills:

Type	Area	Volume	Corrective action	CA Date
------	------	--------	-------------------	---------

☐ Multiple Spills and Releases?

Venting:

Yes/No	Comment

Flaring:

Type	Satisfactory/Action Required	Comment	Corrective Action	CA Date

Predrill

Location ID: 437501

Site Preparation:

Lease Road Adeq.: Pads: Soil Stockpile:

S/A/V:

Corrective Action: Date: CDP Num.:

Form 2A COAs:

Group	User	Comment	Date
OGLA	kubeczkd	Notify the COGCC 48 hours prior to start of pad construction, rig mobilization, spud, and start of hydraulic stimulation operations using Form 42 (the appropriate COGCC individuals will automatically be email notified, including the LGD for hydraulic stimulation operations). As required for Groundwater Baseline Sampling; Operator shall comply with Rule 609. STATEWIDE GROUNDWATER BASELINE SAMPLING AND MONITORING.	09/10/2013

OGLA	kubeczkd	<p>The moisture content of any cuttings in a cuttings pit, trench, or pile shall be as low as practicable to prevent accumulation of liquids greater than de minimis amounts. At the time of closure, if the drill cuttings are to be left onsite, they must also meet the applicable standards of table 910-1.</p> <p>Flowback and stimulation fluids must be sent to tanks, separators, or other containment/filtering equipment before the fluids can be placed into any pipeline, storage vessel, or lined pit (only if an amended Form 2A has been submitted/approved and a Form 15 Earthen Pit Permitted has been submitted/approved) located on the well pad; or into tanker trucks for offsite disposal. The flowback and stimulation fluid tanks, separators, or other containment/filtering equipment must be placed on the well pad in an area with additional downgradient perimeter berming. The area where flowback fluids will be stored/reused must be constructed to be sufficiently impervious to contain any spilled or released material.</p> <p>Operator shall pressure test pipelines in accordance with Rule 1101.e.(1) prior to putting into initial service any temporary surface or permanent buried pipelines and following any reconfiguration of the pipeline network. Operator shall notify the COGCC Oil and Gas Location Assessment (OGLA) Specialist for Western Colorado (Dave Kubeczko; email dave.kubeczko@state.co.us) and the COGCC Field Inspection Supervisor for Northwest Colorado (Shaun Kellerby; email shaun.kellerby@state.co.us) 48 hours prior to testing surface poly or buried steel pipelines.</p> <p>Operator must implement best management practices to contain any unintentional release of fluids along all portions of the surface pipeline route where temporary pumps and other necessary equipment are located.</p> <p>Operator must routinely inspect the entire length of the surface pipeline to ensure integrity. Operator shall conduct daily inspections of surface poly pipeline routes for leaks during active transfer of fluids. Inspections shall be conducted by viewing the length of the pipeline; operator will endeavor to minimize surface disturbance during pipeline monitoring. The operator shall maintain records of inspections, findings and repairs, if necessary, for the life of the pipelines.</p> <p>Operator must ensure appropriate secondary containment for volume of fluids that may be released before pump shut down from the surface pipeline at all stream, intermittent stream, ditch, and drainage crossings. Catchment basins, if needed, should be sized to contain the volume between pump stations or between the nearest pump station and the frac pad being used for this well pad location. Pump stations along the surface poly or steel pipeline route will be continuously monitored when operating in order to swiftly respond to such a failure.</p> <p>Operator will utilize, to the extent practical, all existing access and other public roads, and/or existing pipeline right-of-ways, when placing/routing the surface pipelines. This will reduce surface disturbance and fragmentation of wildlife habitat in the area.</p>	09/10/2013
------	----------	---	------------

OGLA	kubeczkd	<p>Operator must implement best management practices to contain any unintentional release of fluids, including any fluids conveyed via temporary surface pipelines or buried permanent pipelines.</p> <p>Operator must ensure secondary containment for any volume of fluids contained at well site during drilling and completion operations (as shown on the Construction Layout Drawings attachment); including, but not limited to, construction of a berm or diversion dike, diversion/collection trenches within and/or outside of berms/dikes, site grading, or other comparable measures (i.e., best management practices (BMPs) associated with stormwater management) sufficiently protective of nearby surface water. Any berm constructed at the well pad location will be stabilized, inspected at regular intervals (at least every 14 days), and maintained in good condition.</p> <p>The access road will be maintained as to not allow any sediment to migrate from the access road to nearby surface water or any drainages leading to surface water.</p> <p>Berms or other containment devices shall be constructed to be sufficiently impervious (preferably corrugated steel with poly liner) to contain any spilled or released material around crude oil, condensate, and produced water storage tanks.</p>	09/10/2013
------	----------	--	------------

S/A/V: SATISFACTORY**Comment:** COA's met at time of inspection.**CA:****Date:****Wildlife BMPs:**

BMP Type	Comment
Planning	<ul style="list-style-type: none"> * Share/consolidate corridors for pipeline ROWs to the maximum extent possible. * Maximize the utility of surface facilities by developing multiple wells from a single pad (directional drilling), and by co-locating multipurpose facilities (for example, well pads and compressors) to avoid unnecessary habitat fragmentation and disturbance of additional geographic areas. * Minimize newly planned activities and operations within 300 feet of the ordinary high water mark of any reservoir, lake, wetland, or natural perennial or seasonally flowing stream or river. * Locate roads outside of drainages where possible and outside of riparian habitat. * Avoid constructing any road segment in the channel of an intermittent or perennial stream * Avoid new surface disturbance and placing new facilities in key wildlife habitats in consultation with CDOW. * Minimize the number, length, and footprint of oil and gas development roads * Use existing roads where possible * Combine utility infrastructure (gas, electric, and water) planning with roadway planning to avoid separate utility corridors * Combine and share roads to minimize habitat fragmentation * Where possible, consolidate pipeline and existing roadways, or roadways that are planned for development * Maximize the use of directional drilling to minimize habitat loss/fragmentation * Maximize use of remote telemetry for well monitoring to minimize traffic
Wildlife	<ol style="list-style-type: none"> 1. Establish company guidelines to minimize wildlife mortality from vehicle collisions on roads. Slow speeds and increased awareness among employees and contractors traveling to and from the site should help to reduce impacts. 2. Establish a systematic and thorough noxious and invasive weed monitoring and treatment program for all disturbed areas. 3. Reclaim mule deer, elk, and pronghorn antelope habitats with native shrubs, grasses, and forbs appropriate to the ecological site disturbed, avoiding aggressive non-native grasses and shrubs.

Inspector Name: GRANAHAN, KYLE

Interim Reclamation	<ul style="list-style-type: none">* Remove well pad and road surface materials that are incompatible with post-production land use and re-vegetation Requirements.* Use only certified weed-free native seed in seed mixes, except for non-native plants that benefit wildlife* WPX Energy will use certified, weed free grass hay, straw, hay or other mulch materials used for the reseeding and reclamation of disturbed areas.* Install exclusionary devices to prevent bird and other wildlife access to equipment stacks, vents and openings.* Reduce visits to well-sites through remote monitoring (i.e. SCADA) and the use of multi-function contractors.
Drilling/Completion Operations	<ul style="list-style-type: none">* Install and maintain adequate measures to exclude all types of wildlife (e.g., big game, birds, and small rodents) from all fluid pits (e.g., fencing, netting, and other appropriate exclusion measures).Conduct well completions with drilling operations to limit the number of rig moves and traffic.

S/AV: _____ **Comment:** _____

CA: _____ **Date:** _____

Stormwater:

Comment: _____

Staking:

On Site Inspection (305):

Surface Owner Contact Information:

Name: _____ Address: _____

Phone Number: _____ Cell Phone: _____

Operator Rep. Contact Information:

Landman Name: _____ Phone Number: _____

Date Onsite Request Received: _____ Date of Rule 306 Consultation: _____

Request LGD Attendance: _____

LGD Contact Information:

Name: _____ Phone Number: _____ Agreed to Attend: _____

Summary of Landowner Issues:

Summary of Operator Response to Landowner Issues:

Onsite Inspection Memorandum Summarizing Discussions at Inspection as Attachment:

Facility

Facility ID: 437501 Type: WELL API Number: 103-12120 Status: PR Insp. Status: WO

Workover

Comment: Cutters wireline on location to reshoot formation between 13535' & 13393'. Frac crew was not able to move fluid and pressured out 5/23/15. Wireline shot perfs and rigged down and shut well in. Frac to resume on 5/26/15.

Environmental

Spills/Releases:

Type of Spill: _____ Description: _____ Estimated Spill Volume: _____

Inspector Name: GRANAHAH, KYLE

Comment: _____

Corrective Action: _____ Date: _____

Reportable: _____ GPS: Lat _____ Long _____

Proximity to Surface Water: _____ Depth to Ground Water: _____

Water Well:

Lat _____ Long _____

DWR Receipt Num: _____ Owner Name: _____ GPS : _____

Field Parameters:

Sample Location: _____

Emission Control Burner (ECB): _____

Comment: _____

Pilot: _____ Wildlife Protection Devices (fired vessels): _____

Reclamation - Storm Water - Pit

Interim Reclamation:

Date Interim Reclamation Started: _____ Date Interim Reclamation Completed: _____

Land Use: RANGELAND

Comment: _____

1003a. Debris removed? _____ CM _____

CA _____ CA Date _____

Waste Material Onsite? _____ CM _____

CA _____ CA Date _____

Unused or unneeded equipment onsite? _____ CM _____

CA _____ CA Date _____

Pit, cellars, rat holes and other bores closed? _____ CM _____

CA _____ CA Date _____

Guy line anchors removed? _____ CM _____

CA _____ CA Date _____

Guy line anchors marked? _____ CM _____

CA _____ CA Date _____

1003b. Area no longer in use? _____ Production areas stabilized ? _____

1003c. Compacted areas have been cross ripped? _____

1003d. Drilling pit closed? _____ Subsidence over on drill pit? _____

Cuttings management: _____

1003e. Areas no longer needed for drilling or subsequent operations for have been re-vegetated to 80% of pre-existing? _____

Production areas have been stabilized? _____ Segregated soils have been replaced? _____

RESTORATION AND REVEGETATION

Cropland

Top soil replaced _____ Recontoured _____ Perennial forage re-established _____

Inspector Name: GRANAHAH, KYLE

Non-Cropland

Top soil replaced _____

Recontoured _____

80% Revegetation _____

1003 f. Weeds Noxious weeds? _____

Comment: _____

Overall Interim Reclamation _____

Final Reclamation/ Abandoned Location:

Date Final Reclamation Started: _____

Date Final Reclamation Completed: _____

Final Land Use: RANGELAND _____

Reminder: _____

Comment: _____

Well plugged _____

Pit mouse/rat holes, cellars backfilled _____

Debris removed _____

No disturbance /Location never built _____

Access Roads Regraded _____

Contoured _____

Culverts removed _____

Gravel removed _____

Location and associated production facilities reclaimed _____

Locations, facilities, roads, recontoured _____

Compaction alleviation _____

Dust and erosion control _____

Non cropland: Revegetated 80% _____

Cropland: perennial forage _____

Weeds present _____

Subsidence _____

Comment: _____

Corrective Action: _____

Date _____

Overall Final Reclamation _____

Well Release on Active Location ☐

Multi-Well Location ☐

Storm Water:

Loc Erosion BMPs	BMP Maintenance	Lease Road Erosion BMPs	Lease BMP Maintenance	Chemical BMPs	Chemical BMP Maintenance	Comment
Gravel	Pass					
Compaction	Pass					
Berms	Pass					

S/A/V: SATISFACTOR
Y _____

Corrective Date: _____

Comment: No apparent soil migration; erosion or soil movement. BMP's in satisfactory condition at time of inspection.

CA: _____

Pits: ☐ NO SURFACE INDICATION OF PIT