



05-067-07474
Loc # 326394

DATA SHEET FOR DEEP GROUND BED CATHODIC PROTECTION WELLS
NORTHWESTERN NEW MEXICO

Operator Meridian Oil Inc. Location: Unit B Sec. 24 Twp 32 Rng 14

Name of Well/Wells or Pipeline Serviced _____

UTE #19

Elevation _____ Completion Date 9-18-94 Total Depth 373' Land Type I

Casing Strings, Sizes, Types & Depths 9 1/2" Set 99' of 8" PVC Casing.

No Gas, Water, or Boulders Were Encountered During Casing.

If Casing Strings are cemented, show amounts & types used Cemented

With 20 Sacks.

If Cement or Bentonite Plugs have been placed, show depths & amounts used

N/A

Depths & thickness of water zones with description of water: Fresh, Clear,

Salty, Sulphur, Etc. Fresh 200'

Depths gas encountered: N/A

Ground bed depth with type & amount of coke breeze used: 373'

4700 #'s of Loresco

Depths anodes placed: 360, 354, 348, 337, 331, 325, 319, 313, 307, 301, 295, 260, 254, 225, 201

Depths vent pipes placed: 373'

Vent pipe perforations: Bottom 250'

Remarks: _____

If any of the above data is unavailable, please indicate so. Copies of all logs, including Drillers Log, Water Analyses & Well Bore Schematics should be submitted when available. Unplugged abandoned wells are to be included.

Land Type may be shown: F-Federal; I-Indian; S-State; P-Fee.

If Federal or Indian, add Lease Number.