



05-067-07459

LOC # 326093

05-067-05082

LOC # 325012

DATA SHEET FOR DEEP GROUND BED CATHODIC PROTECTION WELLS
NORTHWESTERN NEW MEXICOOperator Meridian Oil Inc. Location: Unit A Sec. 13 Twp 32 Rng 10

Name of Well/Wells or Pipeline Serviced _____

CATet UTE #107 AND Sevet #1Elevation _____ Completion Date 10/26/94 Total Depth 406' Land Type PCasing Strings, Sizes, Types & Depths 10/24 SET 100' OF 8" PVC CASING.NO GAS OR WATER, BUT 36' (27'-63') OF BOULDERS WERE ENCOUNTERED DURING CASING.If Casing Strings are cemented, show amounts & types used CementedWITH 31 SACKS.

If Cement or Bentonite Plugs have been placed, show depths & amounts used

NONE

Depths & thickness of water zones with description of water: Fresh, Clear,

Salty, Sulphur, Etc. HIT FRESH WATER AT 140'. A WATERSAMPLE WAS TAKEN.Depths gas encountered: NONEGround bed depth with type & amount of coke breeze used: 406' DEPTH.USED 84 SACKS OF ASBURY 218R AND 9 SACKS OF LORESCO 9W (5100#)Depths anodes placed: 385', 375', 365', 355', 345', 335', 325', 310', 300', 290', 280', 270', 230', 210', +195'.Depths vent pipes placed: SURFACE TO 406'.Vent pipe perforations: BOTTOM 290'.

Remarks: _____

If any of the above data is unavailable, please indicate so. Copies of all logs, including Drillers Log, Water Analyses & Well Bore Schematics should be submitted when available. Unplugged abandoned wells are to be included.

Land Type may be shown: F-Federal; I-Indian; S-State; P-Free.
If Federal or Indian, add Lease Number.