



LOC # 326287  
05-067-07452  
LOC # 385783

2303W DATA SHEET FOR DEEP GROUND BED CATHODIC PROTECTION WELLS  
NORTHWESTERN NEW MEXICO  
COLORADO

Operator MERIDIAN OIL Location: Unit J Sec. 34 Twp 33 Rng 11

Name of Well/Wells or Pipeline Served UTE 33-11 # 341, A 2

Elevation 6677 Completion Date 10-7-91 Total Depth 338 Land Type I

Casing Strings, Sizes, Types & Depths 67' of 8" PVC SURFACE CASING

If Casing Strings are cemented, show amounts & types used YES with 17 SACKS NEAT CEMENT

If Cement or Bentonite Plugs have been placed, show depths & amounts used NO

Depths & thickness of water zones with description of water: Fresh, Clear, Salty, Sulphur, Etc. 125' FRESH

Depths gas encountered: NO

Ground bed depth with type & amount of coke breeze used: 338' with 2000 lbs LORESCO TYPE SW & 3000 lbs Asbury 4518 FLO COKE

Depths anodes placed: 318, 305, 290, 270, 260, 225, 215, 205, 195, 185, 175, 165

Depths vent pipes placed: 338

Vent pipe perforations: BOTTOM 200'

Remarks: \_\_\_\_\_

If any of the above data is unavailable, please indicate so. Copies of all logs, including Drillers Log, Water Analyses & Well Bore Schematics should be submitted when available. Unplugged abandoned wells are to be included.

Land Type may be shown: F-Federal; I-Indian; S-State; P-Fee.  
If Federal or Indian, add Lease Number.