

# Northmoor Acres 1 05-123-11030 Post-operations WBD (P&A)

12-1/4" Surface Hole

7-7/8" Prod Hole

KB: 5025'

GL: 5013'

8 5/8", 24# Sfc Csg Shoe @ 334'

Fox Hills Marker @ 728'

Sussex Top @ 4128'

No Sussex or Shannon production  
within 1 mile

4 1/2" csg cut off @ 6340"

TOC 6620' (calculated)

NB Top @ 7015'

CIBP @ 7350' capped w/2 sx

Codell perms 7370' - 7384'

4 1/2", 10.5 & 11.6# Prod Csg to 7480'  
TD @ 7480' 02//03/1983

Welded Cap  
Cement to surface

CIBP @ 75'

325 sk cmt plug 950' - 95'  
Type 3 cmt 14.8 ppg, yield=1.33 cf/sk

340 sk cmt plug 4420' - 3740'  
G cmt 15.8 ppg, yield=1.15 cf/sk

100 sk cmt plug 6260' - 6005'  
G cmt 15.8 ppg, yield=1.51 cf/sk

Mud  
Existing Cement  
New Cement

