



Re: CBL deferment on the Federal RU 544-7

1 message

Jay Krabacher <jay.krabacher@state.co.us>

Fri, May 29, 2015 at 1:11 PM

To: "Neifert-Kraiser, Angela" <Angela.Neifert-Kraiser@wpxenergy.com>

Cc: David Andrews - DNR <david.andrews@state.co.us>, "Porraz, Isac" <Isac.Porraz@wpxenergy.com>

Angela:

Looks good. (Keep an eye on the bradenhead-pressure). WPX has COGCC concurrence to defer the CBL on this well.

Regards,

Jay Krabacher

On Fri, May 29, 2015 at 10:53 AM, Neifert-Kraiser, Angela <Angela.Neifert-Kraiser@wpxenergy.com> wrote:

Jay, Dave:

WPX Energy Rocky Mountain, LLC is requesting a CBL deferment on the Federal RU 544-7 located in the Section 7, T 7S-R93W. Attached is a temperature survey that was performed after cementing the 4 ½" production casing on the subject well.

Information pertaining to the request is as follows:

Well:	Federal RU 544-7
API:	05-045-22518-00
Location:	Section 7 T 7S-R93W
Surface Csg:	9 5/8" set and cemented at 1352'
Production Csg Cement Date:	4 ½" @ 10,062' – cemented 5/10/15
Cement:	1060 sks
Cement top from survey:	3525' Estimated
Estimated top of gas:	7167' Estimated
Estimated Top Perf:	6850' Estimated
Temp Survey:	5/10/15 Attached
Volume to fill annular:	Hole remained full following cementing operations

Please let me know if you need additional information to approve this deferment. After deferment is received,

WPX Energy will continue to monitor the bradenhead pressure until the CBL has been performed and notify if pressure exceeds 150 psig.

05/10/2015	22:30	6 HR	0 BBL	21 PSI
05/11/2015	04:30	12 HR	0 BBL	23 PSI
05/11/2015	16:30	24 HR	0 BBL	17 PSI
05/12/2015	16:30	48 HR	0 BBL	15 PSI
05/13/2015	16:30	72 HR	0 BBL	20 PSI

Angela Neifert-Kraiser
303-606-4398
Regulatory Specialist
WPX Energy Rocky Mountain, LLC

If you are inspired, You can do anything!!

—
Jay Krabacher

N W Area Engineer



COLORADO
Oil & Gas Conservation
Commission
Department of Natural Resources

P 970.625.2497 x4

C 970.589.6180

796 Megan Ave., Suite 201, Rifle, CO 81650

jay.krabacher@state.co.us | www.colorado.gov/cogcc