

## Weld County, Colorado, Southern Part

|                                 |
|---------------------------------|
| Wells Ranch AE32-670            |
| Township 6 North, Range 62 West |
| Section 32: SWNW                |
| Weld County, CO                 |

### 70—Valent sand, 3 to 9 percent slopes

#### Map Unit Setting

*National map unit symbol:* 2tczf  
*Elevation:* 3,050 to 5,150 feet  
*Mean annual precipitation:* 12 to 18 inches  
*Mean annual air temperature:* 48 to 55 degrees F  
*Frost-free period:* 130 to 180 days  
*Farmland classification:* Not prime farmland

#### Map Unit Composition

*Valent and similar soils:* 80 percent  
*Minor components:* 20 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Valent

##### Setting

*Landform:* Hills, dunes  
*Landform position (two-dimensional):* Backslope, shoulder, footslope, summit  
*Landform position (three-dimensional):* Side slope, head slope, nose slope, crest  
*Down-slope shape:* Linear, convex  
*Across-slope shape:* Linear, convex  
*Parent material:* Noncalcareous eolian sands

##### Typical profile

*A - 0 to 5 inches:* sand  
*AC - 5 to 12 inches:* sand  
*C1 - 12 to 30 inches:* sand  
*C2 - 30 to 80 inches:* sand

##### Properties and qualities

*Slope:* 3 to 9 percent  
*Depth to restrictive feature:* More than 80 inches  
*Natural drainage class:* Excessively drained  
*Runoff class:* Very low  
*Capacity of the most limiting layer to transmit water (Ksat):* High to very high (6.00 to 39.96 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Calcium carbonate, maximum in profile:* 1 percent  
*Salinity, maximum in profile:* Nonsaline (0.0 to 1.9 mmhos/cm)  
*Available water storage in profile:* Very low (about 2.4 inches)

##### Interpretive groups

*Land capability classification (irrigated):* 4e

Wells Ranch AE32-670  
Township 6 North, Range 62 West  
Section 32: SWNW  
Weld County, CO

*Land capability classification (nonirrigated):* 6e  
*Hydrologic Soil Group:* A  
*Ecological site:* Sands (north) (pe 16-20) (R072XA021KS)

### Minor Components

#### Dailey

*Percent of map unit:* 10 percent  
*Landform:* Interdunes  
*Landform position (two-dimensional):* Footslope, toeslope  
*Landform position (three-dimensional):* Base slope  
*Down-slope shape:* Linear  
*Across-slope shape:* Concave  
*Ecological site:* Sandy (north) draft (april 2010) (pe 16-20) (R072XA022KS)

#### Haxtun

*Percent of map unit:* 5 percent  
*Landform:* Interdunes  
*Landform position (two-dimensional):* Footslope, toeslope  
*Landform position (three-dimensional):* Base slope  
*Down-slope shape:* Linear  
*Across-slope shape:* Concave  
*Ecological site:* Sandy (pe16-20) (south) (formerly sandy, ks - sandy plains, co) (R072XY022KS)

#### Vona

*Percent of map unit:* 5 percent  
*Landform:* Hills  
*Landform position (two-dimensional):* Footslope, backslope, shoulder  
*Landform position (three-dimensional):* Side slope, head slope, nose slope, base slope  
*Down-slope shape:* Linear  
*Across-slope shape:* Linear  
*Ecological site:* Sandy plains (R067BY024CO)

## Data Source Information

Soil Survey Area: Weld County, Colorado, Southern Part  
Survey Area Data: Version 13, Sep 23, 2014

Wells Ranch AE32-670  
Township 6 North, Range 62 West  
Section 32: SWNW  
Weld County, CO

## Weld County, Colorado, Southern Part

### 72—Vona loamy sand, 0 to 3 percent slopes

#### Map Unit Setting

*National map unit symbol:* 363r  
*Elevation:* 4,600 to 5,200 feet  
*Mean annual precipitation:* 13 to 15 inches  
*Mean annual air temperature:* 48 to 55 degrees F  
*Frost-free period:* 130 to 160 days  
*Farmland classification:* Farmland of local importance

#### Map Unit Composition

*Vona and similar soils:* 85 percent  
*Minor components:* 15 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Vona

##### Setting

*Landform:* Terraces, plains  
*Down-slope shape:* Linear  
*Across-slope shape:* Linear  
*Parent material:* Alluvium and/or eolian deposits

##### Typical profile

*H1 - 0 to 6 inches:* loamy sand  
*H2 - 6 to 28 inches:* fine sandy loam  
*H3 - 28 to 60 inches:* sandy loam

##### Properties and qualities

*Slope:* 0 to 3 percent  
*Depth to restrictive feature:* More than 80 inches  
*Natural drainage class:* Well drained  
*Runoff class:* Very low  
*Capacity of the most limiting layer to transmit water (Ksat):* High (1.98 to 6.00 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Calcium carbonate, maximum in profile:* 15 percent  
*Salinity, maximum in profile:* Nonsaline to very slightly saline (0.0 to 4.0 mmhos/cm)  
*Available water storage in profile:* Moderate (about 6.5 inches)

##### Interpretive groups

*Land capability classification (irrigated):* 3e  
*Land capability classification (nonirrigated):* 4e  
*Hydrologic Soil Group:* A  
*Ecological site:* Sandy plains (R067BY024CO)

|                                 |
|---------------------------------|
| Wells Ranch AE32-670            |
| Township 6 North, Range 62 West |
| Section 32: SWNW                |
| Weld County, CO                 |

### Minor Components

#### Remmit

*Percent of map unit:* 10 percent

#### Valent

*Percent of map unit:* 5 percent

## Data Source Information

Soil Survey Area: Weld County, Colorado, Southern Part  
Survey Area Data: Version 13, Sep 23, 2014

Wells Ranch AE32-670  
Township 6 North, Range 62 West  
Section 32: SWNW  
Weld County, CO

## Weld County, Colorado, Southern Part

### 74—Vona loamy sand, 5 to 9 percent slopes

#### Map Unit Setting

*National map unit symbol:* 363t  
*Elevation:* 4,600 to 5,200 feet  
*Mean annual precipitation:* 13 to 15 inches  
*Mean annual air temperature:* 48 to 55 degrees F  
*Frost-free period:* 130 to 160 days  
*Farmland classification:* Not prime farmland

#### Map Unit Composition

*Vona and similar soils:* 85 percent  
*Minor components:* 15 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Vona

##### Setting

*Landform:* Plains  
*Down-slope shape:* Linear  
*Across-slope shape:* Linear  
*Parent material:* Eolian deposits

##### Typical profile

*H1 - 0 to 6 inches:* loamy sand  
*H2 - 6 to 28 inches:* fine sandy loam  
*H3 - 28 to 60 inches:* sandy loam

##### Properties and qualities

*Slope:* 5 to 9 percent  
*Depth to restrictive feature:* More than 80 inches  
*Natural drainage class:* Well drained  
*Runoff class:* Low  
*Capacity of the most limiting layer to transmit water (Ksat):* High (1.98 to 6.00 in/hr)  
*Depth to water table:* More than 80 inches  
*Frequency of flooding:* None  
*Frequency of ponding:* None  
*Calcium carbonate, maximum in profile:* 15 percent  
*Salinity, maximum in profile:* Nonsaline to very slightly saline (0.0 to 4.0 mmhos/cm)  
*Available water storage in profile:* Moderate (about 6.5 inches)

##### Interpretive groups

*Land capability classification (irrigated):* 6e  
*Land capability classification (nonirrigated):* 6e  
*Hydrologic Soil Group:* A  
*Ecological site:* Sandy plains (R067BY024CO)

|                                                                                                |
|------------------------------------------------------------------------------------------------|
| Wells Ranch AE32-670<br>Township 6 North, Range 62 West<br>Section 32: SWNW<br>Weld County, CO |
|------------------------------------------------------------------------------------------------|

### Minor Components

#### Valent

*Percent of map unit:* 10 percent

#### Remmit

*Percent of map unit:* 5 percent

## Data Source Information

Soil Survey Area: Weld County, Colorado, Southern Part

Survey Area Data: Version 13, Sep 23, 2014