

FORM  
2  
Rev  
08/13

State of Colorado  
Oil and Gas Conservation Commission  
1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:  
400818173  
**(SUBMITTED)**

APPLICATION FOR PERMIT TO:

Drill       Deepen       Re-enter       Recomplete and Operate

Date Received:  
05/28/2015

TYPE OF WELL    OIL     GAS     COALBED     OTHER \_\_\_\_\_  
ZONE TYPE      SINGLE ZONE     MULTIPLE ZONES     COMMINGLE ZONES

Refilling   
Sidetrack

Well Name: Wells Ranch      Well Number: AE32-685  
Name of Operator: NOBLE ENERGY INC      COGCC Operator Number: 100322  
Address: 1625 BROADWAY STE 2200  
City: DENVER      State: CO      Zip: 80202  
Contact Name: Andrea Rawson      Phone: (303)228-4253      Fax: (303)228-4286  
Email: arawson@nobleenergyinc.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20030009

WELL LOCATION INFORMATION

QtrQtr: NWNW      Sec: 32      Twp: 6N      Rng: 62W      Meridian: 6  
Latitude: 40.448850      Longitude: -104.354230

Footage at Surface: 576 feet      FNL/FSL      FNL      650 feet      FEL/FWL      FWL

Field Name: WATTENBERG      Field Number: 90750

Ground Elevation: 4748      County: WELD

GPS Data:  
Date of Measurement: 01/07/2015    PDOP Reading: 1.9    Instrument Operator's Name: Adam Kelly

If well is  Directional       Horizontal (highly deviated)      **submit deviated drilling plan.**

Footage at Top of Prod Zone:    FNL/FSL      FEL/FWL      Bottom Hole:    FNL/FSL      FEL/FWL  
330    FNL      535    FEL      330    FNL      535    FEL  
Sec: 32    Twp: 6N    Rng: 62W      Sec: 33    Twp: 6N    Rng: 62W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership:  Fee       State       Federal       Indian

The Surface Owner is:  is the mineral owner beneath the location.  
(check all that apply)  is committed to an Oil and Gas Lease.  
 has signed the Oil and Gas Lease.  
 is the applicant.

The Mineral Owner beneath this Oil and Gas Location is:  Fee       State       Federal       Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: \_\_\_\_\_      Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T6N-R62W, Sec 32: ALL

Total Acres in Described Lease: 640 Described Mineral Lease is:  Fee  State  Federal  Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet  
Building Unit: 5280 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 5280 Feet  
Above Ground Utility: 5280 Feet  
Railroad: 5280 Feet  
Property Line: 576 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a:  Buffer Zone  
 Exception Zone  
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 328 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 535 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

Unit Configuration = T6N-R62W, Sec 28: S/2S/2, 29: S/2S/2, 32: N/2S/2.

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		643	GWA

## DRILLING PROGRAM

Proposed Total Measured Depth: 15992 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 328 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling?     No      
 Will salt based (>15,000 ppm Cl) drilling fluids be used?     No      
 Will oil based drilling fluids be used?     No      
 BOP Equipment Type:  Annular Preventor     Double Ram     Rotating Head     None

**GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING**

Water well sampling required per Rule     318A    

**DRILLING WASTE MANAGEMENT PROGRAM**

Drilling Fluids Disposal:     OFFSITE          Drilling Fluids Disposal Methods:     Recycle/reuse    

Cuttings Disposal:     OFFSITE          Cuttings Disposal Method:     Beneficial reuse    

Other Disposal Description:

Beneficial reuse or land application plan submitted?     Yes    

Reuse Facility ID: \_\_\_\_\_ or Document Number:     2614238    

**CASING PROGRAM**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	0	0	80	6	80	0
SURF	13+3/4	9+5/8	26	0	550	216	550	0
1ST	8+3/4	7	36	0	6798	561	6798	
1ST LINER	6+1/8	4+1/2	11.6	6648	15992			

Conductor Casing is NOT planned

**DESIGNATED SETBACK LOCATION EXCEPTIONS**

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

**GREATER WATTENBERG AREA LOCATION EXCEPTIONS**

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

**RULE 502.b VARIANCE REQUEST**

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments First string top of cement = 200' above the Niobrara formation. The production liner will be hung off inside of the 7" casing string. Four Well Pad including existing Wells Ranch AE32-4 well and new Wells Ranch AE32-690, Wells Ranch AE32-685, and Wells Ranch AE32-675.  
Noble Energy shall isolate the Upper Pierre Aquifer from the Fox Hills Aquifer with surface casing and cement and utilize intermediate casing and cement to ensure isolation from below. The nearest well is the Wells Ranch AE32-685 at 328'.

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: 413709

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Andrea Rawson

Title: Regulatory Analyst I Date: 5/28/2015 Email: Regulatorynotification@noble

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

API NUMBER

05

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

## Best Management Practices

<b>No</b>	<b>BMP/COA Type</b>	<b>Description</b>
1	General Housekeeping	<p><b>GENERAL HOUSEKEEPING:</b>  Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.</p>
2	Storm Water/Erosion Control	<p><b>STORM WATER/EROSION CONTROL:</b>  Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil &amp; Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.</p>
3	Material Handling and Spill Prevention	<p>Spill prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil &amp; Gas operations throughout the state of Colorado in accordance with CFR 112.</p>
4	Drilling/Completion Operations	<p>If a skid is performed for the subject well, then the only required BOPE tests are for the BOPE connection bonnet seal breaks, as long as a full BOPE test was performed at the beginning of the pad, and as long as all necessary BOPE tests are completed at least every 30 days during the pad operations. If a skid is performed for the subject well, then the only required BOPE tests are for the BOPE connection bonnet seal breaks, as long as a full BOPE test was performed at the beginning of the pad, and as long as all necessary BOPE tests are completed at least every 30 days during the pad operations.</p>
5	Drilling/Completion Operations	<p>One of the first wells drilled on the pad will be logged with Cased hole Pulsed Neutron Log with Gamma Ray Log from TD into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run in that well and have those logs attached. The Form 5 for each well shall clearly state "No open-hole logs were run" and shall reference the Rule 317.p Exception granted for the well.</p>

Total: 5 comment(s)

### Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

### Attachment Check List

<b>Att Doc Num</b>	<b>Name</b>
400818173	FORM 2 SUBMITTED
400818748	DEVIATED DRILLING PLAN
400818750	DIRECTIONAL DATA
400842816	OffsetWellEvaluations Data
400844201	WELL LOCATION PLAT
400844206	SURFACE AGRMT/SURETY
400844259	PROPOSED SPACING UNIT
400848715	OPEN HOLE LOGGING EXCEPTION

Total Attach: 8 Files

**General Comments**

<b>User Group</b>	<b>Comment</b>	<b>Comment Date</b>
Permit	Returned to draft for open hole logging exception letter attachment	3/4/2015 9:06:31 AM
Permit	Changed acreage on GWA spacing unit to match the PSU per the operator.	3/4/2015 8:28:34 AM

Total: 2 comment(s)

