

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400842712

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120

2. Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

3. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-

4. Contact Name: ILA BEALE

Phone: (720) 929-6408

Fax:

Email: ila.beale@anadarko.com

5. API Number 05-123-37864-00

7. Well Name: HOWARD

8. Location: QtrQtr: SENW Section: 32 Township: 1N Range: 67W Meridian: 6

9. Field Name: WATTENBERG Field Code: 90750

6. County: WELD

Well Number: 28N-29HZ

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION
Treatment Date: 04/28/2015 End Date: 05/09/2015 Date of First Production this formation: 05/15/2015
Perforations Top: 7953 Bottom: 15164 No. Holes: 864 Hole size: 0.37
Provide a brief summary of the formation treatment: Open Hole: ☐

"PERF AND FRAC FROM 7953-15,164.
131 BBL ACID, 194,287 BBL SLICKWATER, - 194,418 BBL TOTAL FLUID
101,637# 100 MESH OTTAWA/ST. PETERS, 5,696,558# 40/70 GENOA/SAND HILLS, - 5,798,195# TOTAL SAND."

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 194418 Max pressure during treatment (psi): 7749
Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.30
Type of gas used in treatment: Min frac gradient (psi/ft): 0.83
Total acid used in treatment (bbl): 131 Number of staged intervals: 36
Recycled water used in treatment (bbl): 0 Flowback volume recovered (bbl): 1056
Fresh water used in treatment (bbl): 194287 Disposition method for flowback: DISPOSAL
Total proppant used (lbs): 5798195 Rule 805 green completion techniques were utilized: ☒
Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 06/01/2015 Hours: 24 Bbl oil: 76 Mcf Gas: 93 Bbl H2O: 8
Calculated 24 hour rate: Bbl oil: 76 Mcf Gas: 93 Bbl H2O: 8 GOR: 1224
Test Method: FLOWING Casing PSI: 1000 Tubing PSI: Choke Size: 14/64
Gas Disposition: SOLD Gas Type: WET Btu Gas: 1133 API Gravity Oil: 50
Tubing Size: Tubing Setting Depth: Tbg setting date: Packer Depth:
Reason for Non-Production:
Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt
** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: ILA BEALE
Title: STAFF REG. SPECIALIST Date: Email: rscdjpostdrill@anadarko.com

Attachment Check List

Att Doc Num Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)