

## WORKOVER PROCEDURE

**WELL NAME:** Spike State D12-06 **DATE:** 6/9/2015  
**LOCATION:**  
Qtr/Qtr: SENW Section: 12 Township: 3N Range: 64W  
Footages: 1980' FNL & 1980' FWL  
**COUNTY:** WELD **STATE:** CO **API #:** 05-123-17228

**ENGINEER:** AJ Paine 7 Day Notice Sent: \_\_\_\_\_  
(Please notify Engineer of any major changes prior to work) Do not start operations until: \_\_\_\_\_  
Notice Expires: \_\_\_\_\_

**OBJECTIVE:** P&A

**WELL DATA:** Surface Csg: 8 5/8" 24# @ 573' KB Elevation: 4746'  
Surface Cmt: 400 sx GL Elevation: 4736'  
Long St Csg: 2 7/8" 8.7# @ 6986' TD: 6995'  
Long St Cmt: 160 sx + 208 sx PBTD: 6700'  
Long St Date: 8/7/1993  
  
Plug Back (Sand or CIBP): **Retrievable Bridge Plug @ 6700'**  
Perforation Interval (1): Codell Perforations 6823' - 6835'  
Perforation Interval (2): \_\_\_\_\_  
Perforation Interval (3): \_\_\_\_\_  
Tubing: \_\_\_\_\_ Rods: \_\_\_\_\_  
Pump: \_\_\_\_\_  
Misc.: \_\_\_\_\_

**PRODUCTION STATUS:** Well is SI with a hole in the casing.  
**COMMENTS:** No wellhead on this well. 3000# balon ball valve in its place. Must bring spare wellhead.

### PROCEDURE:

- 1) MIRU Workover rig, pump & tank.
- 2) RU; including spare wellhead. RIH w/ workstring and retrieving head & retrieve RBP @ 6700'. POOH w/ RBP.
  - a) If RBP can be retrieved, continue with procedure.
  - b) If RBP can not be retrieved, contact Joe Brnak (970)381-1234 and AJ Paine (406)671-4612
- 3) RU WL. RIH w/ CIBP. Set CIBP @ 6773'
- 4) Pump 11 sx balance plug on top of CIBP. If maintain circulation, no need to tag plug.
- 5) POOH to 4650. Pump 18 sx balance plug. If maintain circulation, no need to tag plug.
- 6) Unland casing. Cut casing off @ 2500'. POOH w/ csg and lay down
- 7) RIH w/ workstring to pump 100 sx stub plug where csg was pulled. If maintain circulation, no need to tag plug.
- 8) POOH w/ workstring to 673'. Pump 250 sx shoe plug. Cement to surface.
- 9) SI, WOC. RIH. Tag shoe plug. Add cement if needed.
- 10) Cut surface casing off 6'-8' below ground.
- 11) Clean up location. Reclaim location. RDMO.