

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400495558

Date Received:

04/28/2014

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 69175

2. Name of Operator: PDC ENERGY INC

3. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

4. Contact Name: Christine Brookshire

Phone: (303) 860-5800

Fax: (303) 860-5838

Email: christine.brookshire@pdce.com

5. API Number 05-123-36954-00

7. Well Name: Waste Management

8. Location: QtrQtr: SWSW Section: 2 Township: 2N Range: 64W Meridian: 6

9. Field Name: DJ HORIZONTAL NIOBRARA Field Code: 16950

6. County: WELD

Well Number: 2i-401

Completed Interval

FORMATION: CODELL Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 09/03/2013 End Date: 09/03/2013 Date of First Production this formation: 09/19/2013
Perforations Top: 7626 Bottom: 11293 No. Holes: Hole size:

Provide a brief summary of the formation treatment:

Open Hole: ☒

16 Stage Codell Completion
3288400 lb Ottawa 20/40
192600 lb SBXL 20/40
Total Fluid 51888
max treatment pressure 8048

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 51888

Max pressure during treatment (psi): 8048

Total gas used in treatment (mcf):

Fluid density at initial fracture (lbs/gal): 8.34

Type of gas used in treatment:

Min frac gradient (psi/ft): 0.64

Total acid used in treatment (bbl):

Number of staged intervals: 16

Recycled water used in treatment (bbl):

Flowback volume recovered (bbl): 14408

Fresh water used in treatment (bbl): 51888

Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 3481000

Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 10/04/2013 Hours: 24 Bbl oil: 269 Mcf Gas: 393 Bbl H2O: 36
Calculated 24 hour rate: Bbl oil: 269 Mcf Gas: 393 Bbl H2O: 36 GOR: 1460
Test Method: Flowing Casing PSI: 1762 Tubing PSI: 794 Choke Size: 16/64
Gas Disposition: SOLD Gas Type: WET Btu Gas: 1547 API Gravity Oil: 45
Tubing Size: 2 + 3/8 Tubing Setting Depth: 7057 Tbg setting date: 09/17/2013 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Christine Brookshire

Title: Regulatory Tech Date: 4/28/2014 Email: christine.brookshire@pdce.com

Attachment Check List

Att Doc Num Name

400495558 FORM 5A SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)