



Wellbore Dia		Price #6-8			
Status	Producing		Operator	Stelbar Oil Corp	
Lease	Price		Zone	Niobrara	
Field	DeNova		API	05-121-09595-00	
State:	Colorado		Division:		
Location	900' FNL & 2000' FWL, NW/4 NE/4 Sec 8-T2S-R49W, 6th PM, Washington County, CO: ? Acre Spacing				
Reference:					
KB	4,389	TVD	3018'	Orig PBTD	2946'
GL	4,383	MTD	3018'	SN	
Casing	Weight/Grade	Depth	Cmt Sx	Hole	TOC
N/A Conductor					
8 5/8"	24#/K-55	287'	210	12 1/4"	Circ
4.5"	10.5#,K-55	3015'	150 sx 50/50 Poz	7 7/8"	TOC Unknown
Spud	12/31/1980		Top Perf	2927'	
Completion	1/6/1981		Bot Perf	2937'	
Perf: 2927'-2937', 10' @ 2 SPF, 20 holes. Stim w/ 40% CO2 water frac w/ 32,400 gals frac fluid, 40,000# 20/40 sand, 50,500# 10/20 sand, 12,000# 8/12 sand, 80 tons CO2					
Date sketch checked		6/10/15	by:	TWL	
Date tubulars checked		6/10/15	by:	TWL	
Current Tubulars					
Tubing String				Length, ft	Depth, ft
Size	Grade	# Jnts	Type		
			KBE	6.00	6.00
2 3/8	J-55	91	Plain Tbg	2859.22	2865.22
2 3/8		1	SN	1.10	2866.32
2 3/8		1	Packer	2.00	2868.32
				0.00	2868.32
					2868.32
Bottom of Tbg String:					2868.32
Rods String				Length, ft	Depth, ft
Size	Grade	# Rods			
Latitude and Longitude Location:					
Latitude:				39.899885	
Longitude:				-102.884581	