

# MARALEX RESOURCES, INC.

Current Wellbore

**WELL NAME** South Shale Ridge 10-15      **COC** 12735  
**LOCATION** NWSE Section 15 T8S R98W 6 PM  
**GPS** 39.358663 -108.314112      **PDOP** 2.5  
**API #** 05-077-08622

**FIELD** South Shale Ridge  
**COUNTY** Mesa  
**GPS OPERATOR** M. Nastal  
**FORMATION** Cameo Coal

**CASING**

**SURFACE**

SIZE & WT 9<sup>5</sup>/<sub>8</sub>" 36#  
 SET @ 133'  
 HOLE SIZE 12<sup>1</sup>/<sub>4</sub>"  
 CEMENT 82 sxs reg.  
w/ 2% CaCl w/ 1/4 #/sx of  
cellophane flakes  
Calculated TOC @ surface

9<sup>5</sup>/<sub>8</sub>" @ 133'

**PRODUCTION**

SIZE & WT 7" 32#  
 SET @ 3184'  
 HOLE SIZE 8<sup>3</sup>/<sub>4</sub>"  
 CEMENT 1st stage: 130 sxs G w/  
2% CaCl      2ond stage: 150 sxs G  
w/ 3% CaCl w/ 12% Calseal & 10#/sx  
Gilsonite      TOC 1st stage (calc)  
2189' 2ond stage(calc) 833'

**STAGE TOOL**

@ 1980'

Stage tool

**OPEN HOLE** 3194'-3291'

**FORMATION TOPS**

Wasatch surface  
 Mesa Verde 1090'  
 Cameo Coals 3162'  
 Rollins 3414'

7" @ 3184'

Cavitated open hole 3194' - 3291'

