

PICEANCE VLY NAD 83

RU 08-07S-093W

RU 21-8 Pad

RU 442-8 - Slot A03

Wellbore #1

Plan: Design #2 14May15 sam

Standard Planning Report

18 May, 2015

WPX

Planning Report

Database:	COMPASS-PICEANCE	Local Co-ordinate Reference:	Well RU 442-8 (A03) - Slot A03
Company:	PICEANCE VLY NAD 83	TVD Reference:	KELLY BUSHING @ 7762.00usft (Nabors 576 (26' RKB) mab)
Project:	RU 08-07S-093W	MD Reference:	KELLY BUSHING @ 7762.00usft (Nabors 576 (26' RKB) mab)
Site:	RU 21-8 Pad	North Reference:	True
Well:	RU 442-8	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #2 14May15 sam		

Project	RU 08-07S-093W		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Colorado Central Zone		

Site						RU 21-8 Pad					
Site Position:		Northing:		1,602,707.70 usft		Latitude:		39.465627			
From:		Map		Easting:		2,350,555.60 usft		Longitude:		-107.800612	
Position Uncertainty:		0.00 usft		Slot Radius:		13.200 in		Grid Convergence:		-1.45	

Well	RU 442-8 - Slot A03					
Well Position	+N/-S	-73.89 usft	Northing:	1,602,635.98 usft	Latitude:	39.465424
	+E/-W	-84.84 usft	Easting:	2,350,468.92 usft	Longitude:	-107.800912
Position Uncertainty		0.00 usft	Wellhead Elevation:	0.00 usft	Ground Level:	7,736.00 usft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	9/8/2014	9.84	65.66	51,918

Design	Design #2 14May15 sam			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (bearing)
	0.00	0.00	0.00	121.76

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
120.00	0.00	0.00	120.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,100.93	31.88	121.76	1,051.09	-139.97	226.11	3.25	3.25	0.00	121.76	
6,520.30	31.88	121.76	5,652.98	-1,646.47	2,659.78	0.00	0.00	0.00	0.00	
8,114.31	0.00	0.00	7,166.00	-1,873.92	3,027.21	2.00	-2.00	0.00	180.00	RU 442-8 TOP GAS 5
10,874.31	0.00	0.00	9,926.00	-1,873.92	3,027.21	0.00	0.00	0.00	0.00	

WPX
Planning Report

Database:	COMPASS-PICEANCE	Local Co-ordinate Reference:	Well RU 442-8 (A03) - Slot A03
Company:	PICEANCE VLY NAD 83	TVD Reference:	KELLY BUSHING @ 7762.00usft (Nabors 576 (26' RKB) mab)
Project:	RU 08-07S-093W	MD Reference:	KELLY BUSHING @ 7762.00usft (Nabors 576 (26' RKB) mab)
Site:	RU 21-8 Pad	North Reference:	True
Well:	RU 442-8	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #2 14May15 sam		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
120.00	0.00	0.00	120.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 3.25									
500.00	12.35	121.76	497.06	-21.47	34.69	40.80	3.25	3.25	0.00
1,000.00	28.60	121.76	963.91	-113.22	182.90	215.11	3.25	3.25	0.00
1,100.93	31.88	121.76	1,051.09	-139.97	226.11	265.93	3.25	3.25	0.00
Hold 31.88 Inclination									
1,300.00	31.88	121.76	1,220.13	-195.31	315.51	371.07	0.00	0.00	0.00
9 5/8"									
1,500.00	31.88	121.76	1,389.96	-250.91	405.33	476.70	0.00	0.00	0.00
2,000.00	31.88	121.76	1,814.54	-389.90	629.86	740.77	0.00	0.00	0.00
2,500.00	31.88	121.76	2,239.12	-528.89	854.39	1,004.84	0.00	0.00	0.00
3,000.00	31.88	121.76	2,663.70	-667.88	1,078.93	1,268.92	0.00	0.00	0.00
3,500.00	31.88	121.76	3,088.27	-806.87	1,303.46	1,532.99	0.00	0.00	0.00
4,000.00	31.88	121.76	3,512.85	-945.87	1,527.99	1,797.06	0.00	0.00	0.00
4,500.00	31.88	121.76	3,937.43	-1,084.86	1,752.53	2,061.13	0.00	0.00	0.00
4,691.45	31.88	121.76	4,100.00	-1,138.08	1,838.50	2,162.25	0.00	0.00	0.00
Top of "G" Sand									
4,826.88	31.88	121.76	4,215.00	-1,175.73	1,899.32	2,233.77	0.00	0.00	0.00
Base of "G" Sand									
5,000.00	31.88	121.76	4,362.01	-1,223.85	1,977.06	2,325.20	0.00	0.00	0.00
5,500.00	31.88	121.76	4,786.58	-1,362.84	2,201.59	2,589.28	0.00	0.00	0.00
6,000.00	31.88	121.76	5,211.16	-1,501.83	2,426.13	2,853.35	0.00	0.00	0.00
6,500.00	31.88	121.76	5,635.74	-1,640.83	2,650.66	3,117.42	0.00	0.00	0.00
6,520.30	31.88	121.76	5,652.98	-1,646.47	2,659.78	3,128.14	0.00	0.00	0.00
Start Drop -2.00									
7,000.00	22.29	121.76	6,079.58	-1,761.29	2,845.26	3,346.29	2.00	-2.00	0.00
7,500.00	12.29	121.76	6,556.39	-1,839.39	2,971.43	3,494.67	2.00	-2.00	0.00
7,809.74	6.09	121.76	6,862.00	-1,865.41	3,013.46	3,544.11	2.00	-2.00	0.00
Mesaverde									
8,000.00	2.29	121.76	7,051.72	-1,872.72	3,025.28	3,558.00	2.00	-2.00	0.00
8,114.31	0.00	0.00	7,166.00	-1,873.92	3,027.21	3,560.28	2.00	-2.00	-106.52
Top Gas Target - Approx. Top Gas									
8,500.00	0.00	0.00	7,551.69	-1,873.92	3,027.21	3,560.28	0.00	0.00	0.00
9,000.00	0.00	0.00	8,051.69	-1,873.92	3,027.21	3,560.28	0.00	0.00	0.00
9,500.00	0.00	0.00	8,551.69	-1,873.92	3,027.21	3,560.28	0.00	0.00	0.00
9,884.31	0.00	0.00	8,936.00	-1,873.92	3,027.21	3,560.28	0.00	0.00	0.00
Cameo Coals									
10,000.00	0.00	0.00	9,051.69	-1,873.92	3,027.21	3,560.28	0.00	0.00	0.00
10,500.00	0.00	0.00	9,551.69	-1,873.92	3,027.21	3,560.28	0.00	0.00	0.00
10,574.31	0.00	0.00	9,626.00	-1,873.92	3,027.21	3,560.28	0.00	0.00	0.00
Coal D									
10,714.31	0.00	0.00	9,766.00	-1,873.92	3,027.21	3,560.28	0.00	0.00	0.00
Rollins SS									
10,864.31	0.00	0.00	9,916.00	-1,873.92	3,027.21	3,560.28	0.00	0.00	0.00
TD									
10,874.31	0.00	0.00	9,926.00	-1,873.92	3,027.21	3,560.28	0.00	0.00	0.00
TD at 10874.31									

WPX

Planning Report

Database:	COMPASS-PICEANCE	Local Co-ordinate Reference:	Well RU 442-8 (A03) - Slot A03
Company:	PICEANCE VLY NAD 83	TVD Reference:	KELLY BUSHING @ 7762.00usft (Nabors 576 (26' RKB) mab)
Project:	RU 08-07S-093W	MD Reference:	KELLY BUSHING @ 7762.00usft (Nabors 576 (26' RKB) mab)
Site:	RU 21-8 Pad	North Reference:	True
Well:	RU 442-8	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #2 14May15 sam		

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (bearing)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
RU 442-8 TOP GAS 50' - plan hits target center - Circle (radius 50.00)	0.00	0.00	7,166.00	-1,873.92	3,027.21	1,600,686.00	2,353,447.70	39.460279	-107.790191

Casing Points					
Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (in)	Hole Diameter (in)	
1,300.00	1,220.13	9 5/8"	9.625	13.500	

Formations						
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (bearing)	
4,691.45	4,100.00	Top of "G" Sand		0.00		
4,826.88	4,215.00	Base of "G" Sand		0.00		
7,809.74	6,862.00	Mesaverde		0.00		
8,114.31	7,166.00	Approx. Top Gas		0.00		
9,884.31	8,936.00	Cameo Coals		0.00		
10,574.31	9,626.00	Coal D		0.00		
10,714.31	9,766.00	Rollins SS		0.00		
10,864.31	9,916.00	TD		0.00		

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
120.00	120.00	0.00	0.00	Start Build 3.25	
1,100.93	1,051.09	-139.97	226.11	Hold 31.88 Inclination	
6,520.30	5,652.98	-1,646.47	2,659.78	Start Drop -2.00	
8,114.31	7,166.00	-1,873.92	3,027.21	Top Gas Target	
10,874.31	9,926.00	-1,873.92	3,027.21	TD at 10874.31	