



Wellbore Dia		State Komatz #1-36			
Status	Producing		Operator	Stelbar Oil Corp	
Lease	State		Zone	Niobrara	
Field	Spear		API	05-121-09594-00	
State:	Colorado		Division:		
Location	1980' FNL & 660' FWL, SW/4 NW/4 Sec 36-T2S-R50W, 6th PM, Washington County, CO: ? Acre Spacing				
Reference:					
KB	4,468	TVD	3043'	Orig PBTD	2985'
GL	4,462	MTD	3043'	SN	
Casing	Weight/Grade	Depth	Cmt Sx	Hole	TOC
N/A Conductor					
8 5/8"	24#/K-55	210'	250	12 1/4"	Circ
4.5"	10.5#,K-55	3013'	150 sx 50/50 Poz	7 7/8"	2590'
Spud	1/3/1981		Top Perf	2935'	
Completion	1/27/1981		Bot Perf	2945'	
Perf: 2935'-2945', 10' @ 2 SPF, 20 holes. Stim w/ 32400 bbls 3% KCL, 80000 lbs CO2, 40K 20/40 sd, 50K 10/20 sd, 10K 8/12 sd					
Date sketch checked		6/10/15	by:	TWL	
Date tubulars checked		6/10/15	by:	TWL	
Current Tubulars					
Tubing String				Length, ft	Depth, ft
Size	Grade	# Jnts	Type		
			KBE	6.00	6.00
2 3/8	J-55	90	Plain Tbg	2911.50	2917.50
2 3/8		1	SN	1.10	2918.60
					2918.60
					2918.60
					2918.60
Bottom of Tbg String:					2918.60
Rods String				Length, ft	Depth, ft
Size	Grade	# Rods			
Latitude and Longitude Location:					
Latitude:				39.838802	
Longitude:				-102.932102	