

Justin Garrett

From: Diana Burn - DNR <diana.burn@state.co.us>
Sent: Thursday, June 25, 2015 11:59 AM
To: John Fink
Cc: Justin Garrett; Steve Jenkins - DNR; Barbara Westerdale - DNR; Jason Kosola - DNR
Subject: EXTERNAL: RE: 70 Ranch State BB18-611 Sidetrack 123-41538

Please proceed as proposed.

Thanks,
Diana

From: John Fink [mailto:John.Fink@nblenergy.com]
Sent: Thursday, June 25, 2015 11:46 AM
To: Diana Burn - DNR
Cc: Justin Garrett
Subject: 70 Ranch State BB18-611 Sidetrack

Diana,

We are requesting permission to sidetrack the 70 Ranch State BB18-611. Please see below my answers to the attached guidance form. I have also attached the sidetrack procedure for you reference.

- i) Trying to run 7" casing in 8.75" OH we were unable to reach TD to set the casing. We were 377' from TD with casing where we encountered difficulty.
- ii) 6952'
- iii) Surface Casing set at 710.9' 9.625" 36#/ft
- iv) No fish in hole
- v) Plug #1: 15.8#/gal 1.51ft3/sk Type G Bottom: 6,840' Height: 700' 52bbls (194sks)
Plug #2: 17.5#/gal 0.94ft3/sk Type G Bottom: 6,140' Height: 650' 48.3bbls (289sks)
- vi) See (v) above
- vii) 5,803' MD proposed KOP
- viii) Same as wellbore being abandoned: Niobrara B Chalk
- ix) Same BHL as abandoned hole

Thanks,

John Fink

Noble Energy
Drilling Engineer
1625 Broadway, Suite 2200
Denver, CO 80202
Office: (720) 587-2081
Cell: (303) 717-1286
John.Fink@nblenergy.com

NOTE NEW EMAIL ADDRESS