

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400842865

Date Received:

05/26/2015

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Anschutz State

Well Number: 5-62-22-4956B2

Name of Operator: BARRETT CORPORATION* BILL

COGCC Operator Number: 10071

Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

Contact Name: Brady Riley

Phone: (303)3128115

Fax: (303)291-0420

Email: briley@billbarrettcorp.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20040060

WELL LOCATION INFORMATION

QtrQtr: SWSW Sec: 22 Twp: 5N Rng: 62W Meridian: 6

Latitude: 40.379522

Longitude: -104.318325

Footage at Surface: 545 feet FNL/FSL FSL 350 feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4682

County: WELD

GPS Data:

Date of Measurement: 03/24/2015 PDOP Reading: 1.3 Instrument Operator's Name: DALLAS NIELSON

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FSL 500 FWL 990 FSL 500 FEL FEL 990 FSL 500 FEL
Sec: 22 Twp: 5N Rng: 62W Sec: 23 Twp: 5N Rng: 62W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☒ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

ALL Section 22, T5N-R62W 6th P.M.

Total Acres in Described Lease: 640 Described Mineral Lease is: ☐ Fee ☒ State ☐ Federal ☐ Indian

Federal or State Lease # CO 8967 6

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet

Building Unit: 5280 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 5280 Feet

Above Ground Utility: 5280 Feet

Railroad: 5280 Feet

Property Line: 350 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 28 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 500 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-1239	1280	all sec 22 & 23

DRILLING PROGRAM

Proposed Total Measured Depth: 16439 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 12 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: ONSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Beneficial reuse

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	9+5/8	36	0	800	430	800	0
1ST	8+3/4	7	26	0	6629	550	6629	600
1ST LINER	6+1/8	4+1/2	11.6	5875	16439	700	16439	5875

☒ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Brady Riley

Title: PERMIT ANALYST Date: 5/26/2015 Email: briley@billbarrettcorp.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 6/26/2015

Expiration Date: 06/25/2017

API NUMBER

05 123 41723 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

- 1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU.
- 2) Comply with Rule 317.j and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Run and submit Directional Survey from TD to base of surface casing. The operator shall comply with Rule 321, and it shall be the operator's responsibility to ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Best Management Practices

No	BMP/COA Type	Description
1	Drilling/Completion Operations	BBC will adhere to the COGCC Policy for Bradenhead Monitoring effective 5/29/12.
2	Drilling/Completion Operations	Anti-collision Mitigation - Prior to drilling operations, Operator will perform a risk analysis of the potential for subsurface collision with existing offset wells within close proximity of the proposed well, taking into consideration the possibility of well path drift for both the existing and proposed wells. Where inclination, MWD or gyro surveys of the offset wells are available, or can be reasonably obtained by the operator, such surveys shall be incorporated in the risk analysis, taking into account survey instrument margin of error. Commission engineering staff shall review and approve the collision risk analysis prior to issuing an approved permit to drill, subject to the operator's right to appeal to the Director or the Commission. For the proposed well, upon conclusion of drilling operations, an as-constructed final directional survey will be submitted to the COGCC with the Form 5.
3	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged with open-hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.

Total: 3 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

Att Doc Num	Name
400842865	FORM 2 SUBMITTED
400842870	DEVIATED DRILLING PLAN
400842871	EXCEPTION LOC REQUEST
400842873	EXCEPTION LOC WAIVERS
400842874	WELL LOCATION PLAT
400842876	STIMULATION SETBACK CONSENT
400842877	OffsetWellEvaluations Data
400842878	DIRECTIONAL DATA

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	6/25/2015 1:49:57 PM
Permit	Operator changed distance to wellbore in formation from 12' to 28'.	6/25/2015 1:27:08 PM
Permit	-Distance from completed portion of wellbore to nearest wellbore permitted or completed in the same formation is incorrect. Contacted operator to correct.	6/25/2015 10:06:28 AM
Engineer	Offset Wells Evaluated	6/16/2015 1:42:30 PM
Permit	Passed completeness	3/2/2015 2:09:19 PM
Permit	Distances to section lines don't match on our maps. Verified with GIS--this is a projection issue with the map. The aerals line up with the operator's distances. Changed attachment "anti-collision Waiver" to "stimulation setback consent"	3/2/2015 2:09:01 PM

Total: 6 comment(s)