

PETROX RESOURCES INC.

DOWNHOLE DIAGRAM & DIMENSIONS

6226'

GROUND

emented to sfc
v/200 sx Type 4-
Equal to Class G)
5.6 ppg,
.18 ft3/sk

JRFACE
ASING: 345 FT
ZE: 9-5/8"
T.: 36#
RADE: S T & C

PRODUCTION
CASING: 2863' FT.
SIZE: 7"
WT.: 20#
GRADE: j-55

Top of Liner: 2427' '
Bottom of Liner 2907'
SIZE: 2-7/8"
WT.: 6.5#
GRADE: J-55
Slotted liner

TD.: 2959
PBDT.: 2427

Formation Tops
Fruitland 2650'-2800
Fruitland Coals
2748'-2792'

Cemented to Surface
w/260 sxs 65/35 POZ
+ 120 sxs Class G
15.6ppg, 1.18 ft3/sk

WINDOW
6.5" O.D.
Lateral
@ 2359--2959"

WELL: TIERRA PIERA 33-5 #15-1R

LOCATION: NWNW SEC 15 T33N-R5W

COUNTY, STATE: ARCHULETA COUNTY, COLORADO

DATE SPUD: 10/20/08

DATE COMPLETED: 10/30/08

CO. SUPERVISOR: MIKE CLARK

TUBING	DATA
SIZE	2-3/8"
WT.	4.7
GRADE	J-55
THDS.	8RD

SUCKER	RODS	
DIA.	NO.	FEET
TOTAL		

ITEM	FEET	JOINTS	MAKE
KB.	16		
TBG	2854		
SUBS - 1-4			
BHA			
SUBS			
TOTAL	2870		

2870'

PUMP	<input type="checkbox"/> ROD	<input type="checkbox"/> SUBMERSIBLE	<input type="checkbox"/> HYDRAULIC
MAKE:	SIZE:		
REMARKS:			

REMARKS: _____
