

**FORM
5**Rev
09/14**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400860956

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 47120

Contact Name: Kayla Hesseltine

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6552

Address: P O BOX 173779

Fax:

City: DENVER State: CO Zip: 80217-

API Number 05-123-40749-00

County: WELD

Well Name: GOODIN

Well Number: 36N-B6HZ

Location: QtrQtr: SWSE Section: 7 Township: 1N Range: 65W Meridian: 6

Footage at surface: Distance: 413 feet Direction: FSL Distance: 1570 feet Direction: FEL

As Drilled Latitude: 40.059841 As Drilled Longitude: -104.702676

GPS Data:

Date of Measurement: 05/01/2015 PDOP Reading: 2.0 GPS Instrument Operator's Name: Carli Sloan

** If directional footage at Top of Prod. Zone Dist.: 207 feet. Direction: FSL Dist.: 2168 feet. Direction: FEL

Sec: 7 Twp: 1N Rng: 65W

** If directional footage at Bottom Hole Dist.: 500 feet. Direction: FSL Dist.: 2134 feet. Direction: FEL

Sec: 6 Twp: 1N Rng: 65W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 12/31/2014 Date TD: 04/11/2015 Date Casing Set or D&A: 04/12/2015

Rig Release Date: 04/28/2015 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 13329 TVD** 7162 Plug Back Total Depth MD 13277 TVD** 7164

Elevations GR 4981 KB 5006 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

CBL, GR

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42.1	0	40	28	0	40	VISU
SURF	13+1/2	9+5/8	36	0	1,580	601	0	1,580	VISU
1ST	8+3/4	7	26	0	7,730	690	158	7,730	CBL
1ST LINER	6+1/8	4+1/2	11.6	6681	13,326	450	6,663	13,326	CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,567				
SHARON SPRINGS	7,267				
NIOBRARA	7,300				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Kayla Hesseltine

Title: Regulatory Specialist

Date: _____

Email: kayla.hesseltine@anadarko.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400860978	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400860975	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400860963	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400860964	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400860965	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400860972	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)