

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400860952

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120

2. Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

3. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-

4. Contact Name: ILA BEALE

Phone: (720) 929-6408

Fax:

Email: ila.beale@anadarko.com

5. API Number 05-123-38982-01

7. Well Name: KERR

8. Location: QtrQtr: SESW Section: 13 Township: 2N Range: 67W Meridian: 6

9. Field Name: WATTENBERG Field Code: 90750

6. County: WELD

Well Number: 28N-12HZX

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION
Treatment Date: 05/31/2015 End Date: 06/14/2015 Date of First Production this formation: 06/19/2015
Perforations Top: 7650 Bottom: 16223 No. Holes: 1032 Hole size: 0.37
Provide a brief summary of the formation treatment: Open Hole: ☐

"PERF AND FRAC FROM 7650-16,223.
417 BBL ACID, 241,001 BBL SLICKWATER, 8,446 BBL TREATED WATER, - 249,863 BBL TOTAL FLUID
7,394,230# 40/70 GENOA/SAND HILLS, - 7,394,230# TOTAL SAND."

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 249863

Max pressure during treatment (psi): 7528

Total gas used in treatment (mcf): 0

Fluid density at initial fracture (lbs/gal): 8.30

Type of gas used in treatment:

Min frac gradient (psi/ft): 0.85

Total acid used in treatment (bbl): 417

Number of staged intervals: 43

Recycled water used in treatment (bbl): 4130

Flowback volume recovered (bbl): 2705

Fresh water used in treatment (bbl): 245317

Disposition method for flowback: RECYCLE

Total proppant used (lbs): 7394230

Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 06/23/2015 Hours: 24 Bbl oil: 16 Mcf Gas: 88 Bbl H2O: 106
Calculated 24 hour rate: Bbl oil: 16 Mcf Gas: 88 Bbl H2O: 106 GOR: 5500
Test Method: FLOWING Casing PSI: 425 Tubing PSI: Choke Size: 14/64
Gas Disposition: SOLD Gas Type: WET Btu Gas: 1408 API Gravity Oil: 48
Tubing Size: Tubing Setting Depth: Tbg setting date: Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: ILA BEALE

Title: STAFF REG. SPECIALIST Date: Email: rscdjpostdrill@anadarko.com

Attachment Check List

Att Doc Num Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)