

Noble Energy, INC
Wells #1
05-123-07365

Proposed Wellbore Schematic

Status - DA
KB elev - 4732'
GL elev - 4722'

8.625" 24#/ft surf csg set @ 105'
w/80sxs cmt to surface

Plug: 200sxs from 500' to surface

Deepest Water well: 305'

Base Fox Hills 339'

Balanced Plug: 100sxs from 3000' to 2650'

No Prod Csg
7.625" open hole to TD

TD = 7170'

Hunter Dunham
3/4/2015