

FORM

2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

400821642

APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate

Date Received:

06/01/2015

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____Refilling ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: Fagerberg Federal

Well Number: I13-685

Name of Operator: NOBLE ENERGY INC

COGCC Operator Number: 100322

Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

Contact Name: Jan Kajiwar

Phone: (303)228-4092

Fax: (303)228-4286

Email: jkajiwar@nobleenergyinc.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20030009

WELL LOCATION INFORMATION

QtrQtr: SWSW Sec: 12 Twp: 6N Rng: 66W Meridian: 6

Latitude: 40.497470

Longitude: -104.733760

Footage at Surface: 690 feet FNL/FSL FSL 340 feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4802

County: WELD

GPS Data:

Date of Measurement: 01/15/2015 PDOP Reading: 2.2 Instrument Operator's Name: Adam Beauprez

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FEL/FWL

 328 FNL 535 FWL 330 FNL 1920 FEL
 Sec: 13 Twp: 6N Rng: 66W Sec: 18 Twp: 6N Rng: 65W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian
 The Surface Owner is: ☐ is the mineral owner beneath the location.
 (check all that apply) ☐ is committed to an Oil and Gas Lease.
☐ has signed the Oil and Gas Lease.☐ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T6-R66W, Sec. 12: SW/4, Sec. 13: W/2NW/4

Total Acres in Described Lease: 240 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 616 Feet
Building Unit: 637 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 327 Feet
Above Ground Utility: 368 Feet
Railroad: 5280 Feet
Property Line: 340 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 01/30/2015

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 329 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 535 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

T6N, R65W, Sec.7: SW/4NE/4, S/2NW/4, SW/4, W/2SE/4, Sec. 18: N/2NW/4, NW/4NE/4, T6N-R66W, Sec. 12: S/2N/2, S/2, Sec. 13: N/2N/2. Spacing unit contains Federal mineral lease C-38564

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-1212	1120	S. 7, 18, 12, 13

DRILLING PROGRAM

Proposed Total Measured Depth: 15564 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 329 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Beneficial reuse

Other Disposal Description:

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: _____ or Document Number: 2614238

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	0	0	80	6	80	0
SURF	13+3/4	9+5/8	36	0	550	216	550	0
1ST	8+3/4	7	26	0	7428	621	7428	
1ST LINER	6+1/8	4+1/2	11.6	7278	15564			

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments 1st String top of cement = 200' above the Niobrara. Production liner will be hung off inside 7" casing. 4 well pad: Fagerberg Federal I12-615, 625, 685, 690. Nearest well = pad well Fagerberg Federal I13-690. Noble Energy shall isolate the Upper Pierre Aquifer from the Fox Hills Aquifer with surface casing and cement and utilize intermediate casing and cement to ensure isolation from below.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jan Kajiwarra

Title: Regulatory Analyst III Date: 6/1/2015 Email: regulatorynotification@nobleen

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 7/10/2015

Expiration Date: 07/09/2017

API NUMBER

05 123 41850 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<u>COA Type</u>	<u>Description</u>
	Operator shall comply with Buffer Zone Move-In, Rig-Up Notice Rule 305.h (effective 9/30/2014).
	<p>Operator acknowledges the proximity of the listed non-producing well(s). Operator agrees to provide mitigation Option 3 (per the DJ Basin Horizontal Offset Policy), ensure all applicable documentation is submitted, and submit Form 42(s) ("OFFSET MITIGATION COMPLETED") for the remediated well(s), referencing the API Number of the proposed horizontal well(s) stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.</p> <p>Farr 1-7-6-65 (API #123-11279) Farr 2-7-6-65 (API #123-11358) Ottoson 4 (API #123-12391) Eisenach 2(API #123-12469)</p>
	<p>Operator acknowledges the proximity of the listed wells. Operator agrees to provide mitigation Option 1 or 2 (per the DJ Basin Horizontal Offset Policy, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42(s) ("OFFSET MITIGATION COMPLETED") for the remediated wells, referencing the API Number of the proposed horizontal well(s) stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.</p> <p>Carlson 1 (API #123-11318) Bailey Federal 1 (API #123-10934) Milne 4 (API #123-12793) Southard 2 (API #123-12378) Ottoson 3 (API #123-12390) Ottoson 1 (API #123-12128) Moore 1 (API #123-12379) Carlson 14-1(API #123-10799)</p>
	<p>1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU. 2) Comply with Rule 317.j and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.</p>

Best Management Practices

No	BMP/COA Type	Description
1	General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
2	Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR- 038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place and maintained until the pad reaches final reclamation
3	Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
4	Drilling/Completion Operations	If a skid is performed for the subject well, then the only required BOPE tests are for the BOPE connection bonnet seal breaks, as long as a full BOPE test was performed at the beginning of the pad, and as long as all necessary BOPE tests are completed at least every 30 days during the pad operations.
5	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged with Cased hole Pulsed Neutron Log with Gamma Ray Log from TD into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run in that well and have those logs attached. The Form 5 for each well shall clearly state "No open-hole logs were run" and shall reference the Rule 317.p Exception granted for the well.

Total: 5 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
2238468	OPEN HOLE LOGGING EXCEPTION
400821642	FORM 2 SUBMITTED
400843865	DEVIATED DRILLING PLAN
400843879	SURFACE AGRMT/SURETY
400843881	WELL LOCATION PLAT
400843884	EXCEPTION LOC WAIVERS
400845460	EXCEPTION LOC REQUEST
400846426	OffsetWellEvaluations Data
400846943	OffsetWellEvaluations Data
400849770	DIRECTIONAL DATA

Total Attach: 10 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	7/9/2015 4:18:37 PM
Permit	Operator referenced wrong DocNum in open hole logging exception request letter. Operator corrected and replaced letter.	7/9/2015 3:07:06 PM
Engineer	Evaluated offset wells. Distance to nearest permitted or existing well penetrating objective formation >150'. No Oil based Mud.	6/26/2015 8:28:59 AM
Permit	passed completeness.	3/8/2015 7:32:10 AM
Permit	returned to draft. Incorrect directional data.	6/5/2015 11:44:34 AM

Total: 5 comment(s)