

MAGNA ENERGY SERVICES LLC

17509 County Road 14

Ft. Morgan, CO 80701

(970) 867-9007

Fax (970) 867-8374

JOB LOG

Rec'd

September 30, 2014

SEP 30 2014

P2

Operator: Foundation Energy

Well: Amoco-Ewing #1

Location: SWSW Sec 30-2N-66W

Weld County, Colorado

API#: 05-123-09875

9-18-14: MIRU. Unseat pump, LD 184 rods & pump. RU for tbg. SWIFN

9-19-14: LD 142 jts 2-3/8 tbg. RU Magna WL. Set CIBP @ 4,541', dump-bailed 2 sxs cement. Perforate well 749'-750' 2 shots. RD WL. RIH with 23 jts tbg. SWIFN

9-22-14: Loaded hole with 5 bbls fresh water, broke circ. Mixed & pumped 40 sxs cement w/calcium chloride, EOT @ 750'. LD 12 jts tbg. Pull EOT to 650'. Loaded hole. Mixed and pumped 20 sxs cement. POOH with 20 jts tbg. SWIFN

9-23-14: PU 15 jts, tag toc @ 485'. LD 12 jts. Load hole, break circ. Mixed and pumped 15 sxs cement. Had cement @ surface. LD tbg. Cut & cap wellhead. RDMO.

All cement used is Class G Neat 15.8#

Cementing contractor: Magna Energy Services

Cementing supervisor: Mike Knighton

Foundation Rep: Jack Rich

Wireline contractor: Magna Wireline