

FORM
5ARev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400870819

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 8960 4. Contact Name: Jessica Azzolina
 2. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY Phone: (720) 440-6100
 3. Address: 410 17TH STREET SUITE #1400 Fax: (720) 279-2331
 City: DENVER State: CO Zip: 80202 Email: jazzolina@bonanzacrk.com

5. API Number 05-123-40197-00 6. County: WELD
 7. Well Name: North Platte Federal Well Number: A-E-22HC
 8. Location: QtrQtr: NWNW Section: 22 Township: 5N Range: 63W Meridian: 6
 9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: CODELL Status: PRODUCING Treatment Type: FRACTURE STIMULATIONTreatment Date: 06/12/2015 End Date: 06/13/2015 Date of First Production this formation: 07/01/2015Perforations Top: 6241 Bottom: 11332 No. Holes: Hole size: 6.125Provide a brief summary of the formation treatment: Open Hole: ☒

25 stage Codell pumped a total of 64,208 bbls of fluid (PermStim) and 3,750,000 # of sand (40/70 Ottawa, 20/40 Ottawa); ATP 4,815 psi, ATR 47 bpm, Final ISDP 3,397 psi; completed with sliding sleeves and casing packers.

This formation is commingled with another formation: ☐ Yes ☒ NoTotal fluid used in treatment (bbl): 64208 Max pressure during treatment (psi): 5128Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.33Type of gas used in treatment: Min frac gradient (psi/ft): 0.94Total acid used in treatment (bbl): 0 Number of staged intervals: 25Recycled water used in treatment (bbl): Flowback volume recovered (bbl): 13174Fresh water used in treatment (bbl): 64208 Disposition method for flowback: DISPOSALTotal proppant used (lbs): 3750000 Rule 805 green completion techniques were utilized: ☐Reason why green completion not utilized: Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 07/03/2015 Hours: 72 Bbl oil: 81 Mcf Gas: 168 Bbl H2O: 1908Calculated 24 hour rate: Bbl oil: 27 Mcf Gas: 56 Bbl H2O: 636 GOR: 2074Test Method: FLOWING Casing PSI: 1325 Tubing PSI: 800 Choke Size: 13Gas Disposition: SOLD Gas Type: WET Btu Gas: 1311 API Gravity Oil: 43Tubing Size: 2 + 3/8 Tubing Setting Depth: 6971 Tbg setting date: 06/21/2015 Packer Depth: Reason for Non-Production: Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt ** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jessica Azzolina

Title: Drilling Technician Date: _____ Email jazzolina@bonanzacrk.com
:

Attachment Check List

Att Doc Num **Name**

--	--

Total Attach: 0 Files

General Comments

User Group **Comment** **Comment Date**

--	--	--

Total: 0 comment(s)