

FORM
5
Rev
09/14

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:
400824057

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

OGCC Operator Number: 47120 Contact Name: Kayla Hesseltnie
 Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6552
 Address: P O BOX 173779 Fax: _____
 City: DENVER State: CO Zip: 80217-

API Number 05-123-40893-00 County: WELD
 Well Name: HUNZIKER Well Number: 1C-28HZ
 Location: QtrQtr: SWSE Section: 28 Township: 2N Range: 67W Meridian: 6
 Footage at surface: Distance: 433 feet Direction: FSL Distance: 1593 feet Direction: FEL
 As Drilled Latitude: 40.103230 As Drilled Longitude: -104.891963

GPS Data:
 Date of Measurement: 06/01/2015 PDOP Reading: 1.0 GPS Instrument Operator's Name: Carli Sloan

** If directional footage at Top of Prod. Zone Dist.: 49 feet. Direction: FSL Dist.: 692 feet. Direction: FEL
 Sec: 28 Twp: 2N Rng: 67W
 ** If directional footage at Bottom Hole Dist.: 461 feet. Direction: FNL Dist.: 542 feet. Direction: FEL
 Sec: 28 Twp: 2N Rng: 67E

Field Name: WATTENBERG Field Number: 90750
 Federal, Indian or State Lease Number: _____

Spud Date: (when the 1st bit hit the dirt) 01/17/2015 Date TD: 03/18/2015 Date Casing Set or D&A: 03/19/2015
 Rig Release Date: 05/29/2015 Per Rule 308A.b.

Well Classification:
 Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

Total Depth MD 12888 TVD** 7677 Plug Back Total Depth MD 12888 TVD** 7677

Elevations GR 5049 KB 5069 **Digital Copies of ALL Logs must be Attached per Rule 308A**

List Electric Logs Run:
CBL, GR, MUD

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42.1	0	40	32	0	40	VISU
SURF	13+1/2	9+5/8	36	0	1,323	514	0	1,323	VISU
1ST	8+3/4	7	26	0	8,124	690	35	8,124	CBL
1ST LINER	6+1/8	4+1/2	11.6	7228	12,873				CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,667				
SHARON SPRINGS	7,499				
NIOBRARA	7,574				
FORT HAYS	7,972				
CODELL	8,024				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Kayla Hesseltine

Title: Regulatory Specialist

Date: _____

Email: kayla.hesseltine@anadarko.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
Attachment Checklist			
400824065	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400824064	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
Other Attachments			
400824060	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400824061	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400824062	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400824063	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400870968	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)