

FORM

2

Rev  
08/13

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

400868240

**(SUBMITTED)**

Date Received:

07/17/2015

## APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate
TYPE OF WELL OIL ☐ GAS ☐ COALBED ☒ OTHER Lateral #1Refilling ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☒Well Name: Lynch 34-6-18Well Number: 1Name of Operator: CATAMOUNT ENERGY PARTNERS LLCCOGCC Operator Number: 10464Address: 1801 BROADWAY #1000City: DENVERState: COZip: 80202Contact Name: Nolan RedmondPhone: (720)484-2344Fax: (720)484-2363Email: nredmond@catamountep.com

## RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20130096

## WELL LOCATION INFORMATION

QtrQtr: SWNW Sec: 18 Twp: 34N Rng: 6W Meridian: MLatitude: 37.193520Longitude: -107.549560
 Footage at Surface: 1774 feet FNL/FSL FNL 211 feet FEL/FWL FWL
Field Name: IGNACIO BLANCOField Number: 38300Ground Elevation: 6858County: LA PLATA

GPS Data:

Date of Measurement: 03/13/2014 PDOP Reading: 2.1 Instrument Operator's Name: Scott WeibeIf well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL FNL 1976 FNL 871 FWL 1951 FNL 681 FEL  
 Sec: 18 Twp: 34N Rng: 6W Sec: 18 Twp: 34N Rng: 6W

## LOCATION SURFACE &amp; MINERALS &amp; RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ IndianThe Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply)

☐ is committed to an Oil and Gas Lease.☐ has signed the Oil and Gas Lease.☐ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ IndianThe Minerals beneath this Oil and Gas Location will be developed by this Well: YesThe right to construct the Oil and Gas Location is granted by: BondSurface damage assurance if no agreement is in place: BlanketSurface Surety ID: 20130097

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

NW/4 S18U T34N R6W

Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 994 Feet  
Building Unit: 994 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 202 Feet  
Above Ground Utility: 891 Feet  
Railroad: 5280 Feet  
Property Line: 171 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 06/11/2014

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 1200 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 681 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
FRUITLAND COAL	FRLDC	112-215	320	N/2

## DRILLING PROGRAM

Proposed Total Measured Depth: 6502 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 1200 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? Yes

Will oil based drilling fluids be used? No

BOP Equipment Type: ☐ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 608

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted?

Reuse Facility ID:  or Document Number:

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	400	155	400	0
1ST	8+3/4	7	20	0	3120	485	3120	0
1ST LINER	6+1/8	2+7/8	6.5	3025	6497			

☒ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

### Comments

This application is for Lateral #1 of the Lynch 34-6-18 #1 API #05-067-09920.  
Drill order will be as follows:  
1 - Lateral #1  
2 - Lateral #1 ST #1  
3 - Lateral #2

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Nolan Redmond

Title: Geo/Eng Tech Date: 7/17/2015 Email: nredmond@catamountep.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

### API NUMBER

05 067 09920 01

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

## Best Management Practices

No	BMP/COA Type	Description
1	Drilling/Completion Operations	Drilling mud or brine will be contained in above ground steel tanks. Drill cuttings and solids that have been separated from the drilling fluid by the shale shakers, mud cleaner or centrifuge will be captured in above ground portable steel cuttings bins and hauled to a 3rd party disposal site that is permitted as required by applicable State and Federal rules and regulations. Excess drilling fluid will be stored in above ground portable steel tanks and will be transferred to the active circulating system as needed. At the completion of drilling activity remaining drilling fluid will be used on another well or disposed of as allowed by Local, State and Federal law. The well pad will have a secondary containment berm to prevent spills, releases, and pollution. The berm will be capable of containing 110% of the fluids stored on location.

Total: 1 comment(s)

## Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

## Attachment Check List



<u>Att Doc Num</u>	<u>Name</u>
400868240	FORM 2 SUBMITTED
400868242	DEVIATED DRILLING PLAN
400868262	DIRECTIONAL DATA
400868264	OTHER
400870295	OffsetWellEvaluations Data
400870296	WELL LOCATION PLAT
400870298	MULTI-WELL PLAN
400870335	WELLBORE DIAGRAM

Total Attach: 8 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	<p>Contacted operator and returned to draft for the following reasons:</p> <ol style="list-style-type: none"> <li>1) Sidetrack should be selected.</li> <li>2) Specify in the comments section the order in which each lateral will be drilled so that the appropriate sidetrack API designation can be input by COGCC.</li> <li>3) Spacing order number is incorrect.</li> <li>4) Input API.</li> </ol>	<p>7/21/2015 8:23:57 AM</p>

Total: 1 comment(s)