

# EnCana Oil & Gas (USA) Inc.

**Well** : SELTZER E UNIT 1  
**Field** : Wattenberg  
**County** : Weld County **State** : Colorado  
**Surface** : Lat: 40.0030820 Long: -104.8708500  
: 990 FSL, 990 FEL, SESE Sec 34 T1N R67W  
**API #** : 05-123-10490  
**Grd Elev** : 5047' GR **KB Elevation:** 5062' KB

## Log Tops:

Fox Hills Base 982'  
Sussex 4708'  
Niobrara 7298'  
Codell 7753'  
J Sand 8193'

## Surface Casing

8-5/8" Surface Casing set  
@ 299', cmt'd w/ 200 sx

TOC @ 7005'  
CBL dated 10/20/1992

## Production Casing

4-1/2" production casing set @ 8340'.  
Cmt w/ 320 sx

## Production Tubing

2-3/8" Tubing set @ 8199'  
262 jts (07/01/2015)

## Well History:

Spud 03/13/82  
TD 03/24/82

Annular fill #6 w/ 20 sx cmt @ 455'  
Annular fill #5 w/ 70 sx cmt @ 768'  
Annular fill #4 w/ 320 sx cmt @ 1237'

Cmt from 1250'-surface  
CBL dated 06/29/2015

Stage Tool @ 1120'  
w/ 1000 gal An-Gel

Annular fill #3 w/ 100 sx cmt @ 4319'  
Annular fill #2 w/ 100 sx cmt @ 4819'  
Annular fill #1 w/ 200 sx cmt @ 5335' Tagged TOC @ 4819'

Cmt from 4208-5330'  
CBL dated 06/29/2015

## Codell Perfs

7753-7776'  
Frac'd with 95,000 gal gel and 290,000#  
20/40 sand (11/04/1992)

## J Sand Perfs

8220-8238'  
Frac'd with 198,500 gal gel and 583,200# 20/  
40 sand (07/08/1982)

TD 8340'

Drawn by:

Scott Reed

Date:

05/22/2015

Revised 7/2/2015

Jane Washburn