

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400863562

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 100322

Contact Name: EILEEN ROBERTS

Name of Operator: NOBLE ENERGY INC

Phone: (303) 2284330

Address: 1625 BROADWAY STE 2200

Fax: (303) 2284286

City: DENVER State: CO Zip: 80202

API Number 05-123-39805-00

County: WELD

Well Name: Davis State

Well Number: LD02-72-1AHN

Location: QtrQtr: SESE Section: 2 Township: 9N Range: 58W Meridian: 6

Footage at surface: Distance: 450 feet Direction: FSL Distance: 371 feet Direction: FEL

As Drilled Latitude: 40.774600 As Drilled Longitude: -103.823000

## GPS Data:

Date of Measurement: 11/17/2014 PDOP Reading: 3.2 GPS Instrument Operator's Name: Toa Sagapolutele

\*\* If directional footage at Top of Prod. Zone Dist.: 1101 feet. Direction: FSL Dist.: 375 feet. Direction: FEL

Sec: 2 Twp: 9N Rng: 58W

\*\* If directional footage at Bottom Hole Dist.: 330 feet. Direction: FNL Dist.: 440 feet. Direction: FEL

Sec: 2 Twp: 9N Rng: 58W

Field Name: WILDCAT

Field Number: 99999

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 12/08/2014 Date TD: 12/13/2014 Date Casing Set or D&amp;A: 12/13/2014

Rig Release Date: 12/14/2014 Per Rule 308A.b.

## Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 9697 TVD\*\* 5547 Plug Back Total Depth MD 9680 TVD\*\* 5547

Elevations GR 4662 KB 4686 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

## List Electric Logs Run:

CBL/Mud/Gamma. Davis State LD 02-72-1AHN

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	84	24	124	80	0	124	VISU
SURF	13+3/4	9+5/8	36	24	1,222	494	0	1,222	VISU
1ST	8+3/4	7	26	24	5,854	430	1,235	5,854	CBL
1ST LINER	6+1/8	4+1/2	11.6	5745	9,682				

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PIERRE	2,329				
PARKMAN	3,196				
SUSSEX	3,803				
SHANNON	4,214				
NIOBRARA	5,693				

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Eileen Roberts

Title: Regulatory Analyst I

Date: \_\_\_\_\_

Email: eroberts@nobleenergyinc.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400863683	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400863688	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400863669	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400863672	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400863673	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400863676	PDF-GAMMA RAY	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400863680	LAS-GAMMA RAY	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400863681	PDF-GAMMA RAY	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400863687	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)